

**RINGKASAN SEBUTHARGA  
SUMMARY OF QUOTATION**

Tajuk / Title **TO CONSTRUCT NEW PLANT HOUSE AT UNIVERSITI BRUNEI DARUSSALAM**  
 Bil. Sebutharga **UBD/Q/149/2022 - [G]**  
 Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(g)
A	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :				
B	<b><u>DEMOLITION AND DISMANTLING WORK</u></b> Supply of labour, materials, tools, etc. to demolish/to properly remove and cut two (2 ) existing plant house structure, aluminum wall panel, existing water tank and structure, sink, temporary disconnect all water supply and etc and make good to all affected area, to provide transport to move all material to UBD Store and disposed all unwanted material /debris to contractor's dump areas per S.O instruction and satisfaction.	Lump		Sum	
C	<b><u>New Plant House (ref. Drawing attached)</u></b> - To design and construct new plant house with brief requirement as below; - Approx. size: 12m x 12m Plant house - 3 zoning area - Structure: GI Metal Structure c/w paint finish. - Grade 25 R.C slab - Wall and roof : P.E Plastic covering c/w metal screen all around the plant house - Fabric insect mesh at upper section for air circulation. - Manually retractable black HDPE anti U.V sun shade as indicate in drawing. - Door: - Supply and install Double Sliding door with plastic covering and metal shade - Supply and install Single Sliding door with plastic covering and metal shade -Supply and install Plastic Strip Door Curtain - PVC gutter - Supply all materials, labour, tools, etc. to lay and fix new s/s water pipe connecting from existing water supply complete with all necessary work required. 4 nos  <b>Note</b> - <b>Please refer to drawing attached for reference</b> - <b>All works to be designed and endorsed by qualified person register under MOD for the purpose of new plant house.</b> - <b>All material and design to be submitted for S.O approval</b>	Lump		Sum	
D	<b><u>Existing Prep Room</u></b> <b><u>Refurbishment of existing prep room</u></b>				
1	To move existing water tank to new position c/w construction of new plinth and base.	LUMP		SUM	
2	To supply and lay FORBO FLOORING SYSTEM or approved equivalent Vinyl flooring for heavy commercial traffic with cushion backing c/w self leveling agent and all necessary accessories and installation is strict accordance to manufacturer's instructions and specification approval and to install new 60mm high, 15mm Thk timber skirting with paint finishes to S.O approve.	M2		27	
3	Supply and install Hanex or approved equivalent solid surface counter top c/w modification of existing RC counter including solid surface wash basin, 75mm Ø discharge drain, bottle trap including assembling and joining together, plugging and screwing or building in screws, hangers, brackets, silicon sealant and all other necessary works required as instructed by S.O.	LUMP		SUM	
4	Supply and install Aluminum powder coated paneling single swing door c/w door jamb, door closer and viewing glass.	Nos		2	
5	Supply and fix 6mm thick Gypsum board ceiling including GI framing system complete with all necessary runners, cross runners, wall angles, rod hangers and hanging wire taping and a 3mm coat of fine gypsum plaster at all joints.				
6	<b>INTERNAL WALL</b> - Supply all labour, materials, tools, etc. to prepare, clean and apply One coat NIPPON Vinilex 5170 (primer for interior/gypsum/plastered) One coat NIPPON Vinilex 5000 (low odour finishing for interior/gypsum/plastered) strict accordance to Manufacturer's instructions; color/brand to S.O.'s approval.	M2		84	
<b>Amount Carried Forward</b>					

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$) (€)
<b>Amount Brought Forward</b>					
7	<b>EXTERNAL WALL</b> - Supply all labour, materials, tools, etc. to prepare, clean and apply One coat NIPPON Weather-bound (finishing for exterior/plastered) One coat NIPPON Vinilex 5101 or Bodelac 9000 (primer for exterior/plastered) strict accordance to Manufacturer's instructions; color/brand to S.O.'s approval.	M2		60	
8	To lay 75mm crusher run using gravel as per drawing c/w installation of filter drain for weep hole along drain. 1000mm (w) 1800mm (w)	M M		30 14	
<b>E</b>	<b>BUILDING SIGNAGE</b>				
1	Design, Fabricate and fix into place new build-up cut -out external wall lettering (signage) using Acrylic signage 20 mm thk <u>Malay lettering</u> and <u>JAWI</u> text include <u>LOGO</u> design and size to S.O approve c/w framing and structure.  300MM (H) <b>فاكولتي ساعين س</b> 150MM (H) <b>Faculty of Science</b> 300MM (H) <b>Plant House</b> <b>Plant house LOGO ( to be confirm)</b>	Lot		1	
<b>F</b>	<b>Electrical work</b>				
	Preparation Room				
1	To supply and install keypad (digital).	LOT		1	
2	To supply, delivery and install 1.5 hp inverter under ceiling air condition Unit c/w wiring control inclusive all fittings and fixtures such as trunking, bracket, support and all necessary accessories including testing and commissioning.	NOS		1	
3	To supply, delivery and install 4.0 mm2 pvc/pvc cable concealed pvc including testing and commissioning.	LOT		1	
4	To replace existing lighting fitting with 1X 36 Watt Led tube with fitting including testing and commissioning.	NOS		2	
5	To supply, delivery and install lighting point using 1.5 mm2 pvc/pvc cable with all necessaries item to complete the work and terminated to nearest DB including testing and commissioning.	LOT		1	
6	To supply, delivery and install one way switch including testing and commissioning.	NOS		3	
7	To supply, delivery and install Fire Extinguisher ABC 4 kg with sign.	NOS		4	
8	To supply, delivery and install weather proof T8 led 1 X36 watt tube with all necessary item including testing and commissioning.	NOS		8	
9	To install 12 inch shutter Exhaust Fan with thermospeed controller, 65 watt, 960 CFM inclusive wiring using 1.5 mm2 pvc/pvc cable and terminated to the nearest DB with fixtures bracket, support and all necessary item to do the work including testing and commissioning.	LOT		2	
10	To upgrade the existing DB to suitable for the new load included additional item such as Mcb, timer and etc.	LOT		1	
11	To supply and install keluar sign with arrow.	NOS		2	
12	To supply and install keluar sign.	NOS		3	
13	To supply, delivery and install weather proof 13Amp power point using 2.5 mm2 pvc/pvc cable concealed 20 mm pvc pipe with all necessary item to complete the work including testing an commissioning.	NOS		7	
14	To supply and install round adjustable airflow stainless steel cone Air vent ceiling grill outlet with ducting size 100 mm. with exhaust fan.	NOS		1	
<b>TOTAL AMOUNT</b>					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....  
(Official Chop / Signature)

---

Liquidated and Ascertained Damages (LAD): **25.00/ day**  
For each day the works remain incomplete  
(If none stated, then the Contract Administrator  
may certify a reasonable sum as compensation  
for delay).

**3 MONTH**

Contract / Address:

.....  
.....  
.....

**\*\* Class : I and above**

**\*\* Category: KA01 B01 E01**

.....  
(Official Chop / Signature)  
Tel. (off) .....  
H/phone .....  
Fax. No .....  
.....