

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **TO SUPPLY AND DELIVER SERVICE OF ROAD MARKING PAINT FOR ROAD KERB AND ROAD LINE, UNIVERSITI BRUNEI DARUSSALAM.**

Bil. Sebutharga **UBD/Q/256/2022 - [G]**

Quotation No.

Page **1** of **2**

Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$) (Ø)
	<p>Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :</p> <p>REPAINTING WORKS</p> <p>*Note: Contractor to engage with painting license applicator and to provide a warranty certificate of at least 5 years upon completion.</p> <p>**Note: Prepare existing surfaces by removal of existing kerb painting and thermoplastic road lane marking of various widths and types and to prepare existing surfaces by removing all dirt and loose particles, jetwash, oil/grease.</p>				
1	<p>Black and White Road Kerb Painting.</p> <p>Painting kerbs with approved water based weather sheild paints to the Standard Specification of the PWD of various types and sizes as follows:(Refer to DRG No : 1 Road Kerb)</p>				
1.1	Zone 1	Lot	1		
1.2	Zone 2	Lot	1		
1.3	Zone 3	Lot	1		
1.4	Zone 4	Lot	1		
1.5	Zone 5	Lot	1		
1.6	Zone 6	Lot	1		
2	<p>White Reflectorised Thermoplastic Road Marking (Refer to DRG No : 2 Road Marking)</p> <p>Supply and lay white reflectorised thermoplastic road markings of various types and sizes as follows:</p> <p>Broken and continuous lines of widths 100mm, 150mm, 200mm, 250mm and 300mm and thickness between 2-4mm.</p> <p>All other marking eg. Marking at the main roundabout, Arrows, junction marking, pedestrian crossing lines, pavement wordings, numbering and symbols. Etc.</p>				
2.1	Zone 1, To include arrows to indicate the junctions at the roundabout as per S.O. Instruction's.	Lot	1		
(Bring forward) Total Page 1:					

Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$)(€)
2.2	Zone 2	Lot	1		
2.3	Zone 3	Lot	1		
2.4	Zone 4	Lot	1		
2.5	Zone 5	Lot	1		
3	Yellow Reflectorised Thermoplastic Road Marking (Refer to DRG No : 3) Supply and lay yellow reflectorised thermoplastic road markings of various types and sizes as follows: Arrows, junction marking, pedestrian crossing lines, pavement wordings, chevrons, numbering and symbols. Etc. Rumble Strips of 5-7mm thick				
3.1	Zone 1	Lot	1		
3.2	Zone 2	Lot	1		
Total Page 2:					
(Bring forward) Total Page 1:					
Subtotal:					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period

3 MONTHS

Contract / Address:

.....
.....
.....

.....
(Official Chop / Signature)

Tel. (off)
H/phone
Fax. No
.....

**** Class : I, II and above**

****Category: B01, KPB 06**