

**RINGKASAN SEBUTHARGA
SUMMARY OF TENDER**

Tajuk / Title **RENOVATION WORKS TO OARA, UNIVERSITI BRUNEI DARUSSALAM**
 Bil. Tawaran **UBD/Q/ 267/2022-[G]**
 Tender No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount	
					(\$)	(€)
	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :					
1	Fabricate, supply and install new 75mm black aluminium powder coated alloy frame partition; infilled with 6mm glass including glazing beads and all other necessary works required.	m2		32		
2	Supply and fix new 12mm gypsum wall partition to both sides, taping and 3mm fine plastering to joints and edges c/w G.I. framing, base detail, approved painting and all other necessary works required.	m2		20		
3	To supply and install single aluminium powder coated alloy frame swing door using 6mm thick glass complete with floor springs, lockset, aluminum handle, patch fitting, weather seal sealant and other necessary fittings and accessories required. Works include to supply and lay decorative film with pattern and design to S.O. approval.	No.s		2		
4	To fabricate and fix steel column stiffener with necessary connection, approved spray painting and all other necessary works required.	No.s		2		
5	To design, supply and install decorative 50% vinyl wall graphic decals/stickers with pattern and design to S.O. approval.	m2		20		
6	To design, supply and install obscure sticker with pattern and design to S.O. approval.	m2		12		
7	To cut-off (shorten) existing existing Reception Counter, design and refurbish as per attached drawing for reference. Design to be submitted to S.O. for approval prior to commencement of work.	Lump		Sum		
8	To supply and install new Zebra Blind; design and pattern to be submitted to S.O. for approval.	m2		41		
	Electrical Works					
9	To supply and install twin socket outlet using 2.5mm2 pvc/pvc cable rings circuit in pvc conduit/trunking with other accessories including hacking works to the floor/wall and make good to complete the work and terminate to the nearest existing Distribution Board.	No.s		24		
10	To supply and install network point using CAT6 Ethernet cable in PVC conduit/trunking complete with its socket outlet including hacking works to the floor/wall and make good of the surfaces.	No.s		10		
11	To supply and install ceiling mounted low noise ventilation fan inclusive of making opening. Noise Level around: 36 (High) 29 (low) including installing flexible aluminum exhaust duct with square louvre for ventilation fan complete with all necessary accessories inclusive of removal/reinstall back ceiling as per original.	Nos		1		
12	To supply and install 3x1.5mm2 PVC cable in PVC conduit for Ventilation fan inclusive of removal/reinstall back ceiling to as per original.	lot		1		
TOTAL AMOUNT						

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
 (Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25/day**
 For each day the works remain incomplete
 (If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period : **1 MONTH**

Contract / Address:

.....

** Class : I and above ** Category: KA01, B01, E01

.....
 (Official Chop / Signature)

Tel. (off)
 H/phone
 Fax. No
