

**ANGGARAN  
SUMMARY OF QUOTATION**

Tajuk / Title **UPGRADING WORKS TO ADMINISTRATION FOYER AT UNIVERSITI BRUNEI DARUSSALAM**

Bil. Tawaran **UBD/Q/328/2022-[G]**

Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$) (%)
	<b>Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :</b>				
<b>1</b>	<b><u>Preparation Work</u></b>				
<b>1.1</b>	Supply of labour, materials, tools, etc. to demolish/to remove, necessary preparation, make good to all affected area disposed all material and cart away all debris to contractor's dump areas per S.O instruction and satisfaction.	Lump		Sum	
<b>1.2</b>	Allow sum for appointment of Competent Designer to design and prepare Architectural drawings and/or detailings for the whole refurbishment works. Also allow for the provision of proposed and as-built drawings.	Lump		Sum	
<b>2</b>	<b><u>Reception Counter</u></b>				
<b>2.1</b>	To design and refurbish existing Reception Counter as per attached drawing for reference. All design and works must include:  - New Glass panel and access door. - Whole back panel of reception counter to use fabric panelling. - Refurbishment of existing counter with necessary modification and to include provision for 2 tablet screen. - Counter toe kick plate. - Façade Panelling for overhead reception counter. - To lay new vinyl flooring with necessary edging according to manufacturer's recommendation and specification.	Lump		Sum	
<b>3</b>	<b><u>Cladding Works</u></b>				
<b>3.1</b>	To prepare surface; Design, supply and fix into place new Alucore type wall cladding to manufacturer's recommendation and specification.	m2		170	
<b>4</b>	<b><u>Vinyl Graphic Infographic</u></b>				
<b>4.1</b>	To design supply and install 100% vinyl graphic decal signage refer drawing.	m2		72	
<b>4.2</b>	To design supply and install 50% vinyl graphic decal signage refer drawing.	m2		72	
<b>4.3</b>	To design and install new Floor "Find and Discover" vinyl graphic signage for following location include to flooring, lift and staircase:  1. Office of Vice Chancellor 2. Office of Assistant Vice-Chancellor 3. Registrar Office 4. SeDIA and Legal Affairs Office 5. Glass Meeting Room 6. Senate Room 7. Meeting Room 1 8. Meeting Room 2 9. Estate Office 10. Administration	Lump		Sum	
<b>5</b>	<b><u>UBD Signage and Logo</u></b>				
<b>5.1</b>	Design, Fabricate and fix into place new build-up cut -out external wall lettering (signage) using Acrylic signage 20 mm thk. Malay lettering and <u>JAWI</u> text include <u>LOGO</u> . design and size to S.O approve.	Lot		1	
<b>5.2</b>	To design and supply Graphic plate design include name of offices/faculties etc with information and QR code. Information required will be provided by S.O.	No.s		39	
<b>Amount Carried Forward</b>					

Bil. No.	Keterangan / Description	Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(€)
<b>Amount Brought Forward</b>					
<b>6</b>	<b>Back Panel</b> To construct new timber back panel with spray paint finished and necessary accessories and works				
<b>6.1</b>	i. Back panel approx size: 1.5m x 2.5m	Nos		4	
<b>6.2</b>	i. Back panel approx size: 1.6m x 3.0m	Nos		2	
<b>7</b>	<b>Painting</b>				
<b>7.1</b>	To prepare surface to be repainted by removal of all loose paints, nail, etc. and plaster / putty all imperfection and sanding to S.O satisfaction to manufacture spec and procedure to main entrance	Lump		Sum	
<b>7.2</b>	Supply all labour, materials, tools, etc. to prepare, clean and apply NIPPON 1 coat of primer sealer, 2 undercoat and 2 finishing coats strict accordance to Manufacturer's instructions; color to S.O.'s approval to main entrance and foyer area as per SO instruction.	Lump		Sum	
<b>8</b>	<b>Bench finishes</b>				
<b>8.1</b>	To supply and fix new timber composite panel and to complete with necessary finishes to existing bench according to manufacturer's recommendation and installation.	m2		45	
<b>TOTAL AMOUNT</b>					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....  
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): 25/day  
For each day the works remain incomplete  
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period : **2 MONTHS**  
+A85

Contract / Address:

.....  
.....  
.....

.....  
(Official Chop / Signature)

Tel. (off) .....  
H/phone .....  
Fax. No .....

\*\* Class : I and above

\*\* Category: B01