

SUMMARY OF QUOTATION

Tajuk / Title REFURBISHMENT AND UPGRADE PREPARATION ROOM B2.36 AND B2.37 FOS, UNIVERSITI BRUNEI DARUSSALAM
 Bil. Sebutharga UBD/Q/331/2022 - (G)
 Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(€)
A	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :				
B	ROOM B2.36 DEMOLITION AND DISMANTLING WORK Supply of labour, materials, tools, etc. to demolish/to properly existing ceiling, pvc pipe, copper pipe, sink, cabinete and etc make good to all affected area, to provide transport to move all material to UBD Store (if required) and disposed all unwanted material /debris to contractor's dump areas per S.O instruction and satisfaction.	Lump		Sum	
C	Refurbishment				
1	To supply and lay FORBO FLOORING SYSTEM or approved equivalent Vinyl flooring for heavy commercial traffic with cushion backing c/w self leveling agent and all necessary accessories and installation is strict accordance to manufacturer's instructions and specification approval and to install new 60mm high, 15mm Thk timber skirting with paint finishes to S.O approve.	m2		35.1	
2	To supply and install 600mm x 600mm aluminum tile ceiling system or approve equivalent, powder coated panel with black acoustic felt complete matching perimeter edge trim, panel carrier and suspensions system, all works to be in accordance with manufactures details and specification.	m2		35.1	
3	To supply and install new sink (deeper sink type) stainless steel c/w pipe, water connection and drain and make good all the affected area.	nos		1	
D	Painting to wall To prepare surface to be repainted by removal of all loose paints, nail, etc. and plaster / putty all imperfection and sanding to S.O satisfaction to manufacture spec and procedure	m2		43	
	Supply all labour, materials, tools, etc. to prepare, clean and apply NIPPON 1 coat of primer sealer, 2 undercoat and 2 finishing coats strict accordance to Manufacturer's instructions; color to S.O.'s approval.	m2		43	
E	New cabinete To construct bottom cabinete and drawer in laminated finish and stainless steel cabinet trim to drawer and doors. Size: 2300mm x 800mm 1500mm x 800mm 2400mm x 800mm	nos nos nos		3 1 1	
F	Emergency shower Emergency shower & eyewash c/w water filter, shower tray, plumbing works and shower curtain.	Unit		1	
G	ROOM B2.37 DISMANTLING WORKS Supply of labour, materials, tools, etc. to demolish/to cut properly existing lab bench and etc make good to all affected area.to move all material to B2.33 and disposed all unwanted material /debris to contractor's dump areas per S.O instruction and satisfaction.	Lump		Sum	
H	Refurbishment				
1	To supply and lay FORBO FLOORING SYSTEM or approved equivalent Vinyl flooring for heavy commercial traffic with cushion backing c/w self leveling agent and all necessary accessories and installation is strict accordance to manufacturer's instructions and specification approval and to install new 60mm high, 15mm Thk timber skirting with paint finishes to S.O approve.	m2		35.1	
2	To supply and install 600mm x 600mm aluminum tile ceiling system or approve equivalent, powder coated panel with black acoustic felt complete matching perimeter edge trim, panel carrier and suspensions system, all works to be in accordance with manufactures details and specification.	m2		35.1	
I	Painting to wall To prepare surface to be repainted by removal of all loose paints, nail, etc. and plaster / putty all imperfection and sanding to S.O satisfaction to manufacture spec and procedure	m2		43	
	Supply all labour, materials, tools, etc. to prepare, clean and apply NIPPON 1 coat of primer sealer, 2 undercoat and 2 finishing coats strict accordance to Manufacturer's instructions; color to S.O.'s approval.	m2		43	
Amount Carried Forward					

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah / Amount (\$) (€)
Amount Brought Forward					
J	ELECTRICAL				
1	To supply and install 13A Twin Switch Socket Outlet c/w additional wiring using 2.5mmsq cable and PVC conduit.	nos		7	
2	To dismantle existing light bulbs and its accessories to LED tube light inside the fitting and modify the wiring and make good of the light fitting after installation.	lot		10	
3	To supply and install 8 inch window mounted exhaust fan including making opening for the glass window.	nos		2	
4	To dismantle existing electric water heater storage including dismantling its piping and accessories and termination of the wiring.	lot		1	
5	To supply & install 3hp cassette type aircon including of its accessories.	no		3	
6	To remove existing fan coil unit including moving of its existing chwp	no		3	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period

2 MONTH

Contract / Address:

.....
(Official Chop / Signature)
Tel. (off) _____
H/phone _____
Fax. No _____

** Class : I and above

** Category: KA01 B01 E01