

RINGKASAN QUOTATION
SUMMARY OF QUOTATION

Tajuk / Title : **URGENT REPLACEMENT WORK OF ARMORED CABLE AT CLT SUB-DISTRIBUTION BOARD
MITSUBISHI THEATRE, UNIVERSITI BRUNEI DARUSSALAM**

Bil. Sebutarga : **UBD/Q/031/2022 (G)**
Quotation No.

Muka page 1 Dari of 1

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah Amount	
					\$	¢
1	To terminate cable terminal, remove and dispose damaged armored cable c/w other accessories.	lot		1		
2	To Supply, laid and install 1x4C/25mm2 XLPE/SWA /PVC +1C 16mm2 PVC ECC cable on cable tray, bracket and support, lugs, glands and all termination work.	m		85		
3	Dismantle and replace existing MCCB and at main switchboard CLT and necessary modification works to mounting and cover.	lot		1		
4	To remove and dismantle existing ceiling for installation of cable for DB CLT FL1, inclusive of reinstallation back and making good of the existing ceiling after cable installation works.	lot		1		
5	Hacking works for 450mm floor slab and making good of floor slabs for the installation of cable for DB CLT FL1.	lot		1		
6	Testing and commissioning complete with configuration of the above works	lot		1		
JUMLAH KESELURUHAN BAGI RINGKASAN TAWARAN INI						
TOTAL AMOUNT FOR THIS SUMMARY OF TENDER						

Contract period:

1 week

Validity Offer:

6 (Six) Months (from closing date of quotation)

From:.....

.....
(Official Chop / Signature)

Contractor / Address:

.....
.....

Class / Category: I and above / E01, E02, M01 / 1 & Above