

Summary Specification		
BIL. SEBUTHARGA/QUOTATION REF.:	UBD/Q/312/2023 (ICTC)-[G]	
BIL. TAWARAN/TENDER REF. :		
TARIKH DIKLANKAN :	16 Januari 2024 [Selasa]	
TARIKH TUTUP :	23 Januari 2024 [Selasa]	JAM: 2 Petang
TARIKH TUTUP :	[Extended]	
TARIKH TUTUP :	[Extended]	
TARIKH TUTUP :	[Extended]	
DOCUMENT FEE :		B\$ 10.00

IMPORTANT

The Official PDF quotation/tender form will be send via email once UBD Official receipt issued and send to vendors/supplier for confirmation of payment received.

Mode of Payments > REFER IN UBD WEBSITE

Please take note that the document fee for each of the New and Extended quotations will be BND 10.00 each

Important Note: Please ensure that you provide the correct details when making the payment.

Please email proof of the above payment to helpdesk.epay@ubd.edu.bn , finance@ubd.edu.bn,eprocurement.support@ubd.edu.bn.

		INSTALLATION, CONFIGURATION, TESTING, COMMISSIONING, INTEGRATION AND MAINTENANCE NETWORK DISTRIBUTION SWITCH FOR ICTC, UNIVERSITI BRUNEI DARUSSALAM
		<ul style="list-style-type: none"> Configure,testing and commissioning Network Distribution switch model 9407 Upgrade all the firmware to latest one for 2 unit supervisor engine,1 unit SFP module 24 port
		<ul style="list-style-type: none"> And 1 unit 48 port RJ45 Vendor shall connect all cable, power on the hardware and delivered hardware equipment in ICTC
		<ul style="list-style-type: none"> Reconfigure all the access switch connection and reconnect the using fibre to new switch 9407 Configure current Vlan ID for Staff and student Vendor shall configure the new hardware to co-exist with the existing hardware infrastructure. This includes network IP and aruba wifi and aruba switch Vendor shall perform the ensure the Modules and integrated and function as it describe into existing UBD Faculties Distribution and Access Switches High availability and redundancy to existng core Switches primary. Supervisor Engines configuration
		<ul style="list-style-type: none"> Network UTP Ports Expansion to other department UTP Network Expansion for DMZ Server Farm Integration The solution must fully integrate with the existing equipment core switch,Wireless, Firewall and UBD's Servers.
		<ul style="list-style-type: none"> The installation shall carried out by local experienced and qualified engineers (Supporting documents such as certifications CCIE to be provided in this Quotation)
		<ul style="list-style-type: none"> The support include with 1 year maintenance for hardware and additional configuration upon request by ICTC Installation must be done after office hours or during public holiday