

Item	Description	Unit	Rate
ZA	TEMPORARY SCAFFOLDING & SAFETY HOARDINGS (Cont'd)		
	Supply and install;		
ZA7	Safety barricades, safety cones, signboard, safety netting or any relevant acceptable safety measures	Lot	\$50.00
ZA8	Heavy duty green canvas inclusive of ropes, pegs and installation	m ²	\$6.00
ZA9	Barrier warning tapes (Red and white colour).	m	\$0.10
	<u>Anti skid tape</u>	m	
ZA10	25mm	m	\$3.00
ZA11	50mm	m	\$5.00
ZA12	100mm	m	\$10.00
	<u>Road Delineator Post</u>		
ZA13	To supply and install new Road Delineator Post with Durable Reflective the following specification Diameter: 80mm High: 700mm-1200mm	no	\$60.00
ZA14	Flexible Pavement <i>Laying, spreading and compacting of asphaltic materials should be done by asphalt supplier / contractor using required or approved asphalt machineries.</i> Supply, deliver, lay and compact 60mm asphaltic concrete base and 40mm thick asphaltic wearing course (thickness after consolidated); laying to slopes, falls and chambers	m ²	\$34.00
	Supply and Bitumen Tack coat to BS3690 standard; application at a rate of 2m ² -3m ²	m ²	\$10.00
* (+) PLUS / (-) MINUS% (.....PERCENTUM)			

Under the terms of the above Quotation respond time for any request/repair work required is within 24hr and completion period in 1 week. Failure to do so, liquidated and ascertained damages will be imposed upon you to amount of \$ 25.00 for each day the works remain incomplete.

This quotation is open to contractor with valid registration minimum class 2 and above, with the Ministry of Development

Defects liability period shall be **3 months**

Contract period:

One (1) year or when the contract amount is not exceeding fifty thousand Brunei dollar (\$50,000.00), which ever come first

Validity Offer:

6 (Six) Months (from the date of quotation)

From:

.....
(Official Chop / Signature)

Contract / Address:

.....
Tel. (off):

.....
H/phone:

.....
Fax. No: