TENDER NO: <u>UBDCORP/Q/002/2024</u> TARIKH DIIKLANKAN: <u>4 JUN 2024[SELASA]</u>

TARIKH TUTUP: 18 JUN 2024[SELASA] JAM 2:00 PETANG

**DOCUMENT FEE: \$20.00** 

## **IMPORTANT**

The official PDF quotation/tender form will be send via email once UBDCorp Official receipt issued and send to vendors/supplier for confirmation of payment received.

Mode of payment REFER IN UBD WEBSITE

Please take note that the document fee for each of the new and extended quotations will be BND \$20.00 each.

<u>IMPORTANT NOTE</u>: Please ensure that you provide the correct details when making the payment. Please email proof of the payment to <u>office.ubdcorp@ubd.edu.bn</u>

Quotation for: <u>TERM CONTRACT OF REPAIR WORKS OF ROOF LEAK AND CEILING AT THE CORE, MALE AND FEMALE RESIDENTIAL COLLEGE, UNIVERSITI BRUNEI DARUSSALAM FOR ONE (1) YEAR</u>

Item no:	Description	Qty.	Unit	Rate
	Supply of labour, materials, tools, equipment, transports, all duty charges and other things deemed necessary to carry out the following works:			
	The proposed water proofing system to be used shall be carried out by licensed applicator approved by the manufacturers of the roofing system i.e. krypton etc. The application of water proofing product shall be in accordance to manufacturer instruction.			
	Note:			
	Contractor shall submit brochures / certificate and other supporting document of proposed water proofing system to be used.			
	Supply of labour, materials, tools, equipment, scaffolding, transport and other things deemed necessary to carried out the following works:			
	ROOF LEAKS.			
1	Investigate the cause of leak and repair roof leaks including replacement of defective ceiling joists, trusses (if any) and other member and to replace with new one. Including sealant application			
	<ul><li>a) At ground floor to 1 storey height</li><li>b) 2 storey height and above (using scaffolding)</li></ul>	Per Per	spot spot	B\$ 89.00 B\$ 110.00
	CEILING			
	Suspended ceiling			
	Replace damaged, missing and stained suspended ceiling similar to existing including extra hanger to follow existing slope and level.			
	Soft Board			
	Size: a) 2' x 2'	1	no	B\$ 7.00
	b) 2' x 4'	1	no	B\$ 11.00
	Cement Board (including painting) Size:			
	a) 2' x 2'	1	no	B\$ 7.00
	b) 2' x 4'	1	no	B\$ 11.00
	<b>Gypsum Board</b> Size:			
	a) 2' x 2'	1	no	B\$ 8.00
	b) 2' x 4'	1	no	B\$ 11.00

Item no:	Description	Qty.	Unit	Rate
2	Non-Suspended ceiling Replace damaged, missing and stained non-suspended ceiling similar to existing including all necessary galvanized metal framing, fastener, hanger to following existing slope and level including painting	1	m²	B\$29.00
3	WATER PROOFING  The proposed water proofing system to be used shall be carried out by licensed applicator approved by the manufactures of the waterproofing system i.e krypton etc. the application of water proofing product shall be in accordance to manufacturer instruction.			
	All electrical services and electrical to be reinstall to its existing position. All equipment's and electrical fittings are contractor liability (protecting and securing)  a) Internal wall b) External wall c) 2 storey height and above (using scaffolding)	1 1 1	m² m² m²	B\$22.00 B\$40.00 B\$50.00
	*Refer to schedule of painting Plaster surface External repainting with 2 coats emulsion ICI (weather shield) paint or approved equivalent.			
	<ul><li>a) External wall</li><li>b) 2 storey height and above (using scaffolding)</li></ul>	1 1	m² m²	B\$16 .00 B\$21.00
	*Contractors shall submit brochures/certificate and other supporting document of proposed water proofing system to be used.			
	INTERNAL REPAINTING *Refer to schedule of painting			
	Plaster surface Internal repainting with 2 coats emulsion ICI (weather shield) paint or approved equivalent.			
	a) Internal wall	1	m²	B\$14.00
	*Contractors shall submit brochures/certificate and other supporting document of proposed water proofing system to be used.			