

**RINGKASAN SEBUTHARGA  
SUMMARY OF QUOTATION**

**Tajuk / Title**                    **REPAIRWORK TO BUSINESS LIBRARY COURTYARD, UNIVERSITI BRUNEI DARUSSALAM**

**Bil. Tawaran**                    **UBD/Q/239/2024-[G]**

Tender No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$) (€)
	<p>Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :</p> <p><b>A    <u>PREPARATION WORK</u></b></p> <p>1    Supply of labour, materials, tools, etc. to demolish/to remove, necessary preparation, make good to all affected area disposed all material and cart away all debris to contractor's dump areas per S.O instruction and satisfaction.</p> <p>2    Supply all materials, labour, plants, etc., to construct 2.4m high temporary hoardings complete with safety signs at the position to be approved by S.O. All hoardings are to be properly maintained and removed on completion of project. NOTE:- Location of the hoarding to be covered at the surrounding site.</p> <p>3    Labour for carefully taking out existing paver block, clean and stack aside for re-use.</p> <p>4    To modify or make good existing RC barrier/edging to the original design.</p> <p>5    Excavate, prepare and lay crushed gravel. Compact the base gravel to accepted level, sloped and establishing an appropriate height.</p> <p>6    To lay sand bedding to compacted gravel and level accordingly.</p> <p><b>B    <u>RELAYING PAVER BLOCK</u></b></p> <p>1    Lay the existing paver blocks to selected pattern and design as approved by S.O. and compact to set the pavers into the sand bedding.</p> <p>2    Lay fine sand evenly to fill the joints of paver blocks.</p>				
		Lump		Sum	
		Lump		Sum	
		Lump		Sum	
		Lump		Sum	
		m2		1599	
		m2		1599	
		m2		664	
		m2		664	
<b>(PAGE 1) TOTAL AMOUNT:</b>					
<b>Bring forward to page 2</b>					

<b>Bil.</b>	<b>Keterangan / Description</b>	<b>Unit</b>	<b>Kadar</b>	<b>Kuantiti</b>	<b>Jumlah</b>
No.		Unit	Rate	Quantity	/Amount (\$) (€)
<b>C</b>	<b><u>TURFING WORKS</u></b>				
1	To supply all necessary tools, labour and equipment to excavate the existing soil with average 150mm deep, cart away, load and dispose off site. To assure no weed stolons and roots will be left at the lawn bedding.	Lump		Sum	
2	Backfill with yellow hill sand min pH5.0 to excavated area, trim to falls and gradient to receive new grass.	m2		935	
3	To mix the washed sand thoroughly with BIO-ROOT Medium (BR4) Organic Soil Conditioner for lawn.	Lump		Sum	
4	Allow for lime and CIRP application for soil acidity adjustment.	Lump		Sum	
5	Supply and install Cow Grass by closed turfing.	m2		935	
<b>C</b>	<b><u>MAINTENANCE</u></b>				
1	To supply supervisor and skilled gardener maintenance service as below:- - Grass cutting and removing of cut grass - Weeding - Fertilizing - Chemical pesticide application - Pruning and trimming - Soil conditioning - Watering as necessary - Removing of green waste	Months		6	
<b>(PAGE 2) TOTAL AMOUNT:</b>					
<b>(PAGE 1) TOTAL AMOUNT:</b>					
<b>TOTAL AMOUNT:</b>					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....  
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): 25/day  
For each day the works remain incomplete  
(If none stated, then the Contract Administrator  
may certify a reasonable sum as compensation  
for delay).

Contract period : **2 MONTHS**

Contract / Address:

.....  
.....  
.....

.....  
(Official Chop / Signature)

Tel. (off) .....  
H/phone .....  
Fax. No .....

\*\* Class : I and above

\*\* Category: