

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **TO SUPPLY AND INSTALL CONSUMPTION LOGGER TO UNIVERSITI BRUNEI DARUSSALAM CAMPUS**

Bil. Tawaran **UBD/Q/240/2024**

Tender No.

| Bil. No. | Keterangan / Description | Unit Unit | Kuantiti Quantity | Kadar Rate | Jumlah /Amount (\$) (€) |
|---|---|--------------|----------------------|---------------|-------------------------------|
| | <p>Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :</p> <p>A</p> <p><u>PREPARATION WORK</u></p> <p>1 To supply and install electrical three phase smart logger c/w all necessary item, bracket, accessories to complete the work including testing per S.O instruction and satisfaction. The scope of work shall included no limited as work below</p> <p>a). To supply and install electrical smart logger that compatible with the JOHNSON CONTROLS" FACILITY EXPLORER BUILDING AUTOMATION SYSTEM Building Management System</p> <p>b). To modified any wiring for electrical work that connected to MCB</p> <p><u>Building Area</u></p> <p>1) SBE</p> <p>2) FASS</p> <p>3) CLT</p> <p>4) SHBIE</p> <p>5) APB</p> <p>6) Administration</p> <p>7) chancellor Hall</p> <p>8) ILIA</p> <p>10) Maintenance Store</p> <p>11) Sport complex</p> <p>12) Male resident Hostel</p> <p>13) Female Residential Hostel</p> <p>14) The core</p> <p>15)Faculty of Integrated Science</p> <p>16) Faculty of Science</p> <p>17) Mosque</p> <p>18) IHS (MAIN)</p> <p>19) IM EXTENSION PAPRSB</p> <p>20) UTH</p> <p>21) Library</p> <p>22)library Extension</p> <p>23)Chiller Yard</p> <p>24) IBER</p> <p>25)MARRIED QUARTER</p> | nos | 25 | | |
| (PAGE 1) TOTAL AMOUNT Bring forward to page 2 | | | | | \$0.00 |

| Bil. No. | Keterangan / Description | Unit Unit | Kuantiti Quantity | Kadar Rate | Jumlah /Amount (\$) (€) |
|------------------------|--|--------------|----------------------|---------------|-------------------------------|
| 2 | To supply and install data interface and flexible pulse output for water meter c/w water meter logger , all necessary item, bracket, accessories to complete the work including testing and commissioning per S.O instruction and satisfaction. The scope of work shall included no limited as work below a).To install flow water meter b). To supply and install water meter data interface and flexible that compatible with the "JOHNSON CONTROLS" FACILITY EXPLORER BUILDING AUTOMATION SYSTEM Building Management System Building Area 1) SBE 2) FASS 3) CLT 4) SHBIE 5) APB 6) Administration 7) chancellor Hall 8) ILIA 10) Maintenance Store 11) Sport complex 12) Male resident Hostel 13) Female Residential Hostel 14) The core 15)Faculty of Integrated Science 16) Faculty of Science 17) Mosque 18) IHS (MAIN) 19) IM EXTENSION PAPRSB 20) UTH 21) Library 22)library Extension 23)Chiller Yard 24) IBER 25)MARRIED QUARTER | nos | 25 | | |
| (PAGE 2) TOTAL AMOUNT: | | | | | |
| TOTAL AMOUNT: | | | | | |

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Stamp / Signature)

Liquidated and Ascertained Damages (LAD): 25/day
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period : **2 MONTHS**

Contract / Address:

.....
.....

.....
** Class : I and above

.....
** Category: B01, M01, & E01, KPB 04, P 05

.....
(Official Stamp / Signature)

Tel. (off)

H/phone

Fax. No