

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **UPGRADING LECTURE THEATRE AT ILIA BUILDING, UNIVERSITI BRUNEI DARUSSALAM.**

Bil. Sebutharga **UBD/Q/245/2024 - [G]**

Quotation No.

Page **1** of **4**

Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$)(€)
	<p>Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including ladder and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :</p> <p>A BUILDING AND CONSTRUCTION</p> <p>1 To prepare surface to be repainted by removal of all loose paints, nail, etc. and plaster / putty all imperfection and to remove one row lecture seats to S.O satisfaction to manufacture spec and procedure</p> <p>2 One coat of Gloss / matt Finish or any other approved equivalent to wood / Timber surfaces. Including Main Door Arch, Doors, Wall Panels and Timber panels. Upon S.O.'s approval.</p> <p>3 Supply all labour, materials, tools, etc. to prepare, clean and apply Juton 1 coat of primer sealer, 2 undercoat and 2 finishing coats strict accordance to Manufacturer's instructions; For Interior and Exterior wall. Color to S.O.'s approval.</p> <p>4 Fabricate, supply and install new gypsum wall and frames Using galvanized iron C channel metal frame, all connections shall be of the same material as the framing system. thickness to S.O approved, all works to be in accordance with manufactures details and specification, Including 2 or 3 coats of Painting. and all other necessary works required.</p> <p>5 To construct new timber table counter for Control Room complete with drawers and formica finish to S.O.'s approval. See Detail 'A' drawing attached.</p> <p>6 To supply and construct new Tinted glass with aluminium frame to S.O.'s approval. See Detail 'A' drawing attached.</p> <p>7 To construct new R.C. concrete stage extentions complete with steps. Height and width is similar to existing, to S.O.'s approval. See 'FLOOR PLAN' drawing attached.</p> <p>B FLOORING</p> <p>1 To remove existing Carpet. All unwanted carpet to be remove off site.</p> <p>2 Supply and install new woven carpet 80% wool 20% nylon 6.6 with back coating Eva Latex 170g/m² 6mm thk rubber underlay and install of aluminum strip, edge and step nosing or equivalent to S.O. approval. Refer to drawing attached for room shape and layout.</p>				
				(PAGE 1) TOTAL AMOUNT: Bring forward to page 4	