

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **RENOVATION TO OFFICE AT AVC ADMINISTRATION BUILDING, UNIVERSITI BRUNEI DARUSSALAM**

Bil. Tawaran **UBD/Q/246/2024 - [G]**

Quotation No.

Page **1** of **3**

Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$) (€)
	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :				
A	PAINTING TO WALL				
1	To prepare surface to be repainted by removal of all loose paints, nail, etc. and plaster / putty all imperfection and sanding to S.O satisfaction to manufacture spec and procedure	Lum	sum		
2	Supply all labour, materials, tools, etc. to prepare, clean and apply Juton 1 coat of primer sealer, 2 undercoat and 2 finishing coats strict accordance to Manufacturer's instructions; color to S.O.'s approval.	Lum	sum		
B	WALL & DOORS				
1	To remove and take out existing Cabinet and make good of the affected area with plastered cement screed and ceiling to be covered and all other necessary works required. As per S.O. instruction.	Lump	sum		
2	Fabricate, supply and install new 75mm aluminium powder coated alloy frame wall ; infilled with 6mm glass including glazing beads and all other necessary works required.	M ²	32.71		
3	Fabricate, supply and install new gypsum wall both sides and frames Using galvanized iron C channel metal frame, Infill with insulation wool or the likes. All connections shall be of the same material as the framing system. thickness to S.O approved, all works to be in accordance with manufactures details and specification, Including 2 or 3 coats of Painting. and all other necessary works required.	M ²	43.03		
4	To remove existing internal brick wall for Door including hacking and make good of the affected walls and floor area with plastered cement screed as per S.O. instruction.	Lot	1		
5	To supply and install new single leaf aluminium powder coated alloy frame door with glass panel including lockset, door handle and heavy duty floor type hinges. Works shall include Hacking, preparing, sealing and other necessary accessories required as per S.O. instruction.	Nos	5		
6	To construct new timber back panel feature wall with spray paint finished and necessary accessories and works	M ²	8.7		
(PAGE 1) TOTAL AMOUNT:					
Bring forward to page 2					