

**RINGKASAN QUOTATION**  
SUMMARY OF QUOTATION

**Tajuk / Title** : **TO SUPPLY AND INSTALL AUTOMATED BARRIER AT MAIN SECURITY POST AND UNIVERSITI BRUNEI DARUSSALAM MAIN ROAD**

**Bil. Sebutharga** : **UBD/Q/254/2024 (G)**  
Quotation No.

Muka page 1 Dari of 2

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah Amount	
					\$	¢
1.1	<b>MAIN SECURITY GUARD HOUSE</b> To supply, deliver and install automatic barrier with 1 piece single 6 mtrs arm with reflective red/white color, bottom side mounted with rubber protection, reflective " STOP" sign mounted on aluminum backing size 300x300mm c/w Dc control, 40KA lighting surge arrestor 10A 2P MCB, DC arm motor with 5 million MTCF, all necessary wiring for the operation of remote control and accessories required	lots		2		
1.2	Supply, install automatic barrier waterproof up/down push button control at guard house using 1x4c/2.5mm PVC/SWA/PVC armored cable laid on cable tray/ underground inclusive of saw cut and breaking of concrete on walkway/main road, installation of pipe sleeve/crossing excavation of turf, earth backfilling with sand, installation of cable marker all along the cable route, all making good works inclusive of disposed off all excess dirt, concrete/asphalt using quick cure cement mortar to seal-off the saw cut groove	lots		2		
1.3	Supply, install 1x2c/2.5mm PVC/SWA/PVC armoured cable laid on cable tray/underground inclusive of saw cut and breaking of concrete on walkway/main road, installation of pipe sleeve/crossing excavation of turf, earth backfilling with sand, installation of cable marker all along the cable route inclusive of all making good works, disposed off all excess dirt, concrete/asphalt debris using quick cure cement motor to seal-off the saw cut groove	lots		2		
1.4	Excavation for the installation of concrete foundation/raise up plinth painted with 2 coat of hazard colour code surrounding 2 or 4 side of the automatic barrier for the installation of items 1 above and pvc bend elbow conduit pipe provision of CCTV and making good surrounding area according to S.O instruction	lot		2		
1.5	Upgrading of existing Guard House switch board, all necessary modification with 2P MCB's inclusive replacing insulated busbar, inclusive of supply and install new metalclad DB for access barrier with 2P 20A MCB, 2P 30Ma 40A RCD and insulated busbar with outgoing 2x10A 2P MCB's contactor, control and emergency key with ON/OFF push button and submain wiring from existing Guard House switchboard and all labelling works	lot		1		
1.6	To Fabricated, supply , delivery and install reflective SIGNAGE design or lettering is according to S.O instruction example SLOW DOWN wording on the road and others.	lot		1		
<b>JUMLAH KEESELURUHAN BAGI MUKA SURAT 1</b>						
<b>TOTAL AMOUNT FOR PAGE 1</b>						

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah Amount	
					\$	¢
2.1	<b>UNIVERSITI BRUNEI DARUSSALAM MAIN ROAD</b> To supply, delivery and install automatic barrier with 1 piece single 6 mtrs arm with reflective red/white color, bottom side mounted with rubber protection, reflective ' STOP ' sign mounted on aluminum backing size 300x300mm c/w 240V Ac control, 40KA lighting surge arrestor 10A 2P MCB, AC arm motor with minimum 5 million MTCF, AC loop relays and all necessary wirings for the operation of remote control and accessories required.	lots		2		
2.2	To break concrete and excavation for the installation of concrete foundation/raise up plinth painted with 2 coat of harzad colour code surrounding 2 or 4 sides of the automatic barrier for the installation of items 1 above and pvc bend elbow conduit pipe provision of CCTV and making good surrounding area.	lots		2		
2.3	Supply, install 1x2c/4.0mm PVC/SWA/PVC armoured cable laid on underground inclusive of saw cut and breaking of concrete, installation of pipe sleeve/crossing excavation of turf, earth backfilling with sand, installation of cable marker all along the cable route inclusive of all making good works, disposed off all excess dirt, concrete/asphalt debris.	lots		2		
2.4	To supply and install solar harzad warning flashing LED light c/w 50mm diameter pole mounted on concrete plinth.	lots		4		
2.5	To Fabricated, supply, delivery and install reflective SIGNAGE design or lettering is according to S.O instruction example SLOW DOWN wording on the road and others	lots		2		
2.6	To supply, programme and deliver remote control c/w batteries	sets		6		
3	Testing and commissioning for all the above works	lot		1		
<b>JUMLAH KEESELURUHAN BAGI MUKA SURAT 2</b>						
TOTAL AMOUNT FOR PAGE 2						
<b>JUMLAH KEESELURUHAN BAGI RINGKASAN TAWARAN INI</b>						
TOTAL AMOUNT FOR THIS SUMMARY OF TENDER						

Contract period:

**1 month**

Validity Offer:

6 (Six) Months (from closing date of quotation)

From:.....

.....  
(Official Chop / Signature)

Contractor / Address:

.....

.....

Tel. (off):.....

H/phone:.....

Class / Category: I and above / E01,E02 / 1 & Above