

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **TO SUPPLY, DELIVER COMPLETE WITH INSTALLATION CASSETTE TYPE UNIT AIRCONDITIONING UNIT FOR CHEMISTRY LABORATORIES, FACULTY OF SCIENCE, UNIVERSITI BRUNEI DARUSSALAM**

Bil. Sebutharga **UBD/Q/295 /2024-[G]**

Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(€)
1	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :	lot		1	
2	To supply and install fixed speed 3hp Cassette type unit (R32 refrigerant) c/w wireless remote control inclusive all fittings and fixtures such as trunking, bracket, support, hanger and all necessary accessories drain pipe c/w insulation, Please attach brand make offer and warranty	nos		5	
3	Cost for hacking, hole opening and making good the surface of opening for glass window and brick wall supply and install refrigerant pipes and condensate pipes	lots		5	
4	Supply and install refrigerant pipes and condensate drain pipe c/w insulation	lots		5	
5	Supply and install power and control cabling from distribution board to condensing unit and fan coil unit c/w isolator, trunking, cable tray and accessories	lots		5	
6	Supply, install and upgrading Residual Current Device (RCD) for individual AC unit at distribution board c/w wiring and necessary works	lots		5	
7	Flushing, vacuuming, top up gas and necessary works to the unit	lots		5	
8	Testing and commissioning all above the works	lot		1	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

1 week

Contract / Address:

.....
.....
.....

.....
(Official Chop / Signature)

Tel. (off)

H/phone

Fax. No

Class and Category: 1 and above / E01, E02,M01