

TENDER NO: UBDCORP/Q/001/2025.

DIKLANKAN: 25/02/2025 2025[SELASA]

TARIKH TUTUP: 11/03/2025[SELASA] JAM 2:00 PETANG

DOCUMENT FEE: \$20.00

IMPORTANT

The official PDF /tender form will be send via email once UBDCorp Official receipt issued and send to vendors/supplier for confirmation of payment received.

Mode of payment REFER IN UBD WEBSITE

Please take note that the document fee for each of the new and extended quotations will be BND \$20.00 each.

IMPORTANT NOTE:

Please ensure that you provide the correct details when making the payment. Please email proof of the payment to office.ubdcorp@ubd.edu.bn and contact 673 8721450

TITLE: TO SUPPLY, DELIVER, AND INSTALL OF AIR CONDITIONING UNIT (FOR THE CORE), ELECTRICAL WORKS, PARTITIONING & ALUMINIUM GLASS WORKS.

REF: UBDCORP/Q/001/2025

PG 1 OF 2

NO	DESCRIPTION	QUANTITY	UNIT	RATE	AMOUNT
1	AIR- CONDITIONING INSTALLATION				
	To supply and install 5HP Cassette type air-conditioning.	5	SET		
	To supply & install additional refrigerant piping with insulation form and wiring.	120	M		
	To supply and install new water drain PVC piping with insulation form.	120	M		
2	ELECTRICAL WORK				
	To supply and layout wiring for new air conditioning power supply point 5x4mm Sq Pvc Cable complete with 32 Amp 3 phase isolator	5	NOS		
	To supply and install 63 Amp 13-way DB box complete with main power supply cable	1	NOS		
	To supply and install 28-way DB box complete with MCB 20 Amp (10 Nos), 10 Amp (10 Nos) and 32 Amp (5 Nos)	1	LOT		
	To supply and install air curtain 3(feet) for doors open areas (Totaline)	8	NOS		
	To supply and install wiring for air gutter power point (2.5mm wire)	6	NOS		

TITLE: TO SUPPLY, DELIVER, AND INSTALL OF AIR CONDITIONING UNIT (FOR THE CORE), ELECTRICAL WORKS, PARTITIONING & ALUMINIUM GLASS WORKS.

REF: UBDCORP/Q/001/2025

PG 2 OF 2

NO	DESCRIPTION	QUANTITY	UNIT	RATE	AMOUNT
3	PARTITION AND ALUMINIUM GLASS WORK				
	To supply and install brick work partition with fixed aluminium glass partition	5	SET		
	To supply and install aluminium sliding door with 8mm thick clear glass	120	M		
		120	M		
TOTAL AMOUNT					