

**RINGKASAN SEBUTHARGA  
SUMMARY OF QUOTATION**

Tajuk / Title                      **REPLACEMENT OF LED LIGHTING AT INSTITUTE OF HEALTH SCIENCE EXTENSION, UNIVERSITI BRUNEI DARUSSALAM**

Bil. Sebutharga                      **UBD/Q/088/2025-[G]**

Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah / Amount (\$)(£)
	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :				
1	To remove, take down existing light fittings, bulbs and its accessories and to dispose away from UBD.	lum		sum	
	<b>*Note To contractor to attach catalog/specification of light offered.</b>				
2	<b><u>I.H.S Extension Level 2 Corridor</u></b>				
a	Supply, deliver and install <b>6" 12W LED downlight</b> , aluminium diecast body, white trim, <b>CT 5000,Lifespan 50,000Hrs with IP20 driver</b> and all necessary accessories, all installation works done at high level.	150		nos	
b	Supply, deliver and install <b>8" 18W LED downlight</b> , aluminium diecast body, white trim, <b>CT 5000,Lifespan 50,000Hrs with IP20 driver</b> and all necessary accessories, all installation works done at high level.	57		nos	
c	To supply and install new 20A 3 pole contactors	15		nos	
d	To supply and install new 16A timer	4		nos	
3	<b><u>I.H.S Extension Level 3 Concourse and Corridor</u></b>				
a	Supply, deliver and install <b>10" 50 W LED downlight, aluminium diecast body, white trim, CT 5000,Lifespan 50,000Hrs with IP65 driver</b> and all necessary accessories <b>including fabricating the bracket for the light fitting</b> , all installation works done at high level.	32		nos	
b	Supply, deliver and install <b>6" 12W LED downlight</b> , aluminium diecast body, white trim, <b>CT 5000,Lifespan 50,000Hrs with IP20 driver</b> and all necessary accessories, all installation works done at high level.	35		nos	
c	Supply, deliver and install <b>8" 18W 280/250 LED downlight</b> , aluminium diecast body, white trim, <b>CT 5000,Lifespan 50,000Hrs with IP20 driver</b> and all necessary accessories, all installation works done at high level.	90		nos	
d	To supply and install new 20A 3 pole contactors	12		nos	
e	To supply and install new 16A timer	1		no	
4	<b><u>I.H.S Extension Level 4 Corridor</u></b>				
a	Supply, deliver and install <b>8" 18W LED downlight</b> , aluminium diecast body, white trim, <b>CT 5000,Lifespan 50,000Hrs with IP20 driver</b> and all necessary accessories, all installation works done at high level.	38		nos	
b	To supply and install new 20A 3 pole contactors	6		nos	
c	To supply and install new 16A timer	2		nos	
5	Testing and commissioning all above the works	1		lots	
<b>TOTAL AMOUNT</b>					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....  
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**  
For each day the works remain incomplete  
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

**1 week**

Contract / Address:

.....  
.....  
.....

.....  
(Official Chop / Signature)

Tel. (off)

H/phone

Fax. No

.....  
.....  
.....

**Class and Category: 1 and above / E01, E02**