

SUMMARY OF TENDER

Tajuk / Title TO CONSTRUCT NEW VENDOR BOOTH AT INSTITUTE OF HEALTH SCIENCES EXTENSION BUILDING , UNIVERSITI BRUNEI DARUSSALAM.

Bil. Tawaran UBD/Q/212/2025 - [T]

Tender No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(g)
	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :				
1	<u>VENDOR BOOTH (Ref Pic as reference only)</u>				
1.1	Allow sum for appointment of Competent Designer to design and prepare Architectural drawings and/or detailings for the whole Vendor Booth.	LUMP		SUM	
1.2	To construct vendor booths (café) modern design 'U' shape counter with solid surface countertop c/w base cabinetries in laminate finish to S.O. approval. Approx size: 3500mm x 2600mm	LUMP		SUM	
1.3	Ditto but new back counter include decorative backsplash, single approve sink, pull-out kitchen faucet c/w all necessary fittings, water supply and sink trap connection to the nearest existing services.To ripped up part of floor, cut a trench or Concrete Coring to existing floor slab method for conduit and drain pipe, laid new tiling to match existing design or make good affected area. Approx size: 3500mm x 2600mm	LUMP		SUM	
1.4	To fabricate and install new back wall panel using plywood c/w laminate finish.	M2		9.45	
1.5	To fabricate and install shelving to existing window.	LUMP		SUM	
1.6	Supply and fix new gypsum board ceiling, taping and 3mm fine plastering to joints and edges c/w G.I framing, shadow gap, ceiling pelmet, edge trim, approved painting and all other necessary works required.	M2		8.75	
1.7	To intsaill raise 100mm thk floor using 18mm cementboard c/w glue adhesive and GI hollow framing c/w anti corrosive paint.	M2		8.75	
1.8	To install SPC Flooring with cushion backing/underlay and all necessary accessories and installation is strict accordance to manufacturer's instruction and specification approval and to install new 60mm high, 15mm thk timber skirting with paint finishes to S.O approve.	M2		8.75	
2	<u>M&E</u>				
2.1	To supply and install neon lighting with multi color design to S.O approve c/w all necessary connection. Approx. size : 800mm x 800mm	LOT		1	
2.2	To Supply Deliver and Install custom 13A twin switch socket outlet (BS1363 type) using 2.5mm2 pvc/pvc cable concealed complete with connection to DB included to install 10AMP Mcb. Complete with floor and wall hacking and make good.	NOS		5	
2.3	To Supply Deliver and Install custom 20A single switch socket outlet (BS1363 type) using 4mm2 pvc/pvc cable concealed complete with connection to DB included to install 32AMP Mcb. Complete with floor and wall hacking and make good.	NOS		2	
2.4	To Supply & Install 10w LED Down light 70mm diameter (warm light) with Electrical Cabling Points C/W one gang one way switch using 2.5 mm2 pvc/pvc cable concealed.	NOS		7	
2.5	To supply and install LED flexible Neon Strips including driver high lumen 12v/24v and connected to the nearest DB design to be approved by S.O.	M		12	
2.6	Supply and install fire blanket approve as approve by Fire and Rescue Department	NO		1	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

Liquidated and Ascertained Damages (LAD): 25/day For each day the works remain incomplete (If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period :

2 MONTHS

Contract / Address:

.....

.....
 (Official Stamp / Signature)
 Tel. (off)
 H/phone
 Fax. No

** Class : I and above ** Category: KA01, B01, E01