

Summary Specification	
BIL. SEBUTHARGA/QUOTATION REF.:	UBD/Q/233/2025 (ICTC) - [G]
TARIKH DIKLANKAN :	16 Disember 2025 [Selasa]
TARIKH TUTUP :	30 Disember 2025 [Selasa] JAM: 2 Petang
DOCUMENT FEE : B\$ 10.00	

IMPORTANT

The Official PDF quotation/tender form will be send via email once UBD Official receipt issued and send to vendors/supplier for confirmation of payment received.

Please take note that the document fee for each of the New and Extended quotations will be BND 10.00 each

a) Quotations or tenders under Universiti Brunei Darussalam (Kerajaan) can be identified by the letter [G] at the end of the quotation/tender reference number.

Example: UBD/Q/123/2023 – [G]

b) Quotations or tenders under Universiti Brunei Darussalam (Tabung UBD) can be identified by the letter [T] at the end of the quotation/tender reference number.

Example: UBD/Q/123/2023 – [T]

Please ensure that your company makes payment to the correct account:

For [G] references → Kerajaan Account

For [T] references → Tabung Universiti Account

Account numbers and detailed payment steps are available on the Universiti Brunei Darussalam website under the section "Mode of Payment."

Important Note: Please ensure that you provide the correct details when making the payment.

Please email proof of the above payment to helpdesk.epay@ubd.edu.bn , finance@ubd.edu.bn, eprocurement.support@ubd.edu.bn.

TITLE :		TO SUPPLY AND INSTALL NEW FIBER OPTIC BACKBONES FOR HEP , CORPORATE SERVICE OFFICE AND ICTC, UNIVERSITI BRUNEI DARUSSALAM.
No.	Quantity	SPECIFICATIONS
1		HEP – First Floor to Ground Floor (HEP New Datacom Room)
	1 Lot	To supply & install 24C outdoor SM Fiber Optic cable Cable run in exposed PVC conduit/casing/trunking inclusive of hauling. (Total cable length not exceeding 200m)
	2	24 port SC SM FO patch panel - Rackmount
	2	24 port SC SM FO patch panel - Wallmount
	6	Supply & install SM Duplex Fiber Patch Cord (SC/LC) – 1 meter
2		CSO – First Floor to Groud Floor (HEP New Datacom Room)
	1 Lot	To supply & install 6C outdoor SM Fiber Optic cable Cable run in exposed PVC conduit/casing/trunking inclusive of hauling. (Total cable length not exceeding 120m)
	2	6 port SC SM FO patch panel - Rackmount
	2	Supply & install SM Duplex Fiber Patch Cord (SC/LC)-1 meter
3		ICTC1 to ICTC Server Room
	1 Lot	To supply & install 6C outdoor SM Fiber Optic cable Cable run in exposed PVC conduit/casing/trunking inclusive of hauling. (Total cable length not exceeding 120m)
	2	6 port SC SM FO patch panel - Rackmount
	3	Supply & install SM Duplex Fiber Patch Cord (SC/LC)-1 meter
4	1 Lot	Scope of work :
		Termination of SM FO cable to be carried out by certified installer
		Test report and labelling at both ends
		Carry out tests using FLUKE DSX5000 tester or equivalent for all FO cables to ensure compliance with EIA/TIA 568 standard. Test results will be submitted for verification and record
		Warranty : The 20 years warranty shall be a transferable warranty and inclusive of component replacement and labour cost to replace any defective components