

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **TO SUPPLY AND INSTALL SPLIT UNIT A/C AT FIRST FLOOR AVC OFFICE ADMIN BUILDING, UNIVERSITI BRUNEI DARUSSALAM**
Bil. Tawaran **UBD/Q/242/2025-[G]**
Tender No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(€)
1	To supply, delivery and install 2.5 hp cassette type c/w 20 amps switch with 32 Amp Isolator point using 4.0 mm2 pvc/pvc cable and other assessories, bracket and items including drain pipe with insulation etc.. to complete the work and terminate to the nearest existing Distribution Board.	nos		3	
2	To supply, delivery and install 3 hp cassette type c/w 32A isolator outlet point using 4.0 mm2 pvc/pvc cable and other assessories, bracket and items including drain pipe with insulation etc... to complete the work and terminate to the nearest existing Distribution Board.	nos		1	
3	To upgrade Existing DB suitable for additional new Split unit c/w all assesories (such as MCB, copper bar and etc) and material including all accessories, new wiring and items to complete the work including testing and commissioning.	lot		1	
4	To remove the existng affected ducting and disposed all material and cart away all debris to contractors dump area out from site pe S.O instruction and satisfaction	lot		1	
5	To install new ducting suit to the new design, approved by S.O	lot		1	
6	To make good all the the affected and surrounding area (including hacking, painting, plastering, replace any item to new one)	lot		1	
TOTAL AMOUNT:					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Stamp / Signature)

Liquidated and Ascertained Damages (LAD): 25/day
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period : **2 MONTHS**

Contract / Address:

.....
(Official Stamp/ Signature)

Tel. (off)
H/phone
Fax. No

** Class : I and above

** Category:E01, E02 & M01