

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **SUPPLY AND INSTALL LED STREET AND COMPOUND LIGHTS AT VARIOUS LOCATIONS AT UNIVERSITI BRUNEI DARUSSALAM**

Bil. Sebutharga **UBD/Q/260/2025-[G]**
Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(€)
	Supply of labour, materials, tools, etc. to demolish, to remove, necessary preparation, make good to all affected area disposed all material and cart away all debris to contractors dump area out from site pe S.O instruction and satisfaction Note: The contractor shall carry out site visit inspection and take into account all aspects and conditions of site before submitting his quotation. The contractor must fill this schedule at the time of tendering. Contractor having submitted their prices are considered as having visited the site. No claims for additional payment will be entertained on the ground of misunderstanding or misinterpretation of the conditions, measurement etc.				
1	Removal and dispose of unserviceable/damage street light fitting, pole supply cables, damage street lighting cables, street light cut-out and MCBs away from UBD site.	L.S			
2	Supply and install 150W LED energy efficient street light lantern , IP65, IK08, ≥16500 lumens, CCT 4000K, CRI ≥80Ra, PF ≥0.90, die-cast aluminium body, surge protection, Ta +50oC.	nos		40	
3	Supply and install 2Cx2.5mm2 PVC/PVC cable c/w ECC for 150W street light lantern, all necessary accessories and termination works.	nos		40	
4	Supply and install weatherproof street lighting cut out (DES approved brand) with 2x10A MCB c/w all necessary accessories and termination works.	nos		4	
5	Supply and install 10A MCB (ABCI approved brand) with all necessary accessories and termination works.	nos		36	
6	To check and troubleshoot existing faulty LV underground cable for street lighting scope and inclusive but unlimited if necessary, replace with new LV cable for the faulty cable c/w excavation works, cable marker, sand bedding remove and dispose of excess earth, make good excavated area, concreting, put back turf if required.	lot		1	
7	To check and make good all existing street lighting control and replace faulty parts of each component MCCB, MCB, contactors and other accessories.	L.S			
8	To supply and install digital timer c/w accessories inclusive of removal of existing faulty timer and any modification works required.	nos		2	
9	To supply and replace with 30W-50W E27 LED bulb 4000K and new base holder for compound lights.	nos		53	
10	To supply and replace with new AC contactor in feeder pillar.	no		1	
11	To make good and re-align compound light pole	lot		1	
12	Rental of cherry picker and operator for the above works.	lot		1	
13	Testing and commissioning works for the above.	no		1	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period
2 weeks

Contract / Address:

.....
.....
.....

.....
(Official Chop / Signature)
Tel. (off)
H/phone
Fax. No

Class and Category: 1 and above / E01, E02, M01