

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title TO REPLACE THE EXISTING VIP LIFT AT CHANCELLORY HALL, UNIVERSITI BRUNEI DARUSSALAM

Bil. Tawaran UBD/Q/283/2025 - [1]

Tender No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$) (€)
1	<p>To supply, delivery, install new passenger lift c/w labour and material, item such as hook, trimmer-beam, c-channel, l beams, guide rail support and other item no specified herein but necessary to complete the installation the work included testing and commissioning . The Scope of work shall also including not limited to fabrication, interior design (design as per s.o approval). The specifications should be as below: -</p> <p>a) Duty Load: - 1600kg / appro. 21 pax</p> <p>b) Speed:- 1.6 m/s</p> <p>c) Control: Single Full Collective / 3 Phase 50Hz</p> <p>d) No. of Floor / Level: - B, G & 1</p> <p>e) No. of Stop / Opening: - 3 / 3</p> <p>f) Travel: 16400 mm</p> <p>g) Overhead: 4500 mm</p> <p>h) Pit Depth: 2000 mm</p> <p>ij) Cage Clear Size (Internal): 1750 mm (W) x 2000 mm (D) 2350 mm (H)</p> <p>j) Door Opening Size: 1100 mm (W) x 2100 mm (H)</p> <p>k) VIP mode/ auto attended button</p> <p>l) Emergency battery operated power source complete with necessary</p> <p>m) exhausted</p>	lot		1	
2	To dismantle the existing lift and put away from the site to the scrape yard or contractor site dump area.	lot		1	
3	To supply and install emergency battery operated power source complete with necessary accessories and lead acid sealed maintenance free batteries.	lot		1	
4	To supply and install 2000mm (length) x 400mm (wide) hot dipped galvanised steel cat ladder.	lot		1	
5	To provide Bureau Veritas Test report.	lot		1	
6	To Supply and install with new 20A 3 poles MCCB 3 Phase 50Hz 240V tap from the existing MCCB at existing lift machine room at Basement Floor to Top Floor. This include enclosed with metal distribution Box connecting using armoured cable 1 x 4C/6.0mm ² pvc cable with PVC Casing enclosure inside the lift shaft to Top Floor.	lot		1	
7	To supply New Distribution Board suitable for the new lift c/w 40A 0.03A RCD, 1 x 40A TP MCB, 1 x 20A TP MCB, 1 x Surge Protector including incoming 4 Core Armoured 6.0mm ² SWA/PVC Cable in concealed inside.	lot		1	
(PAGE 1) TOTAL AMOUNT:					
Bring forward to page 2					

Bil. No.	Keterangan / Description	Unit	Kadar	Kuantiti	Jumlah /Amount
		Unit	Rate	Quantity	(\$) (€)
8	To do make good and painting to match existing finished of all affected area	lot		1	
9	To supply and install lift intercom system to be located at the security counter at chancellory hall	lot		1	
10	<p>Trade off</p> <p>Trade off all reusable material on site for the contractor to revalue /salvage. Allow for all cost salvaging all material values and other related materials from the above demolition works, including transportation and clear the site as per S.O instructions. This amount is deductible to the above amount of this works. item must be priced and considered as discount.</p> <p>Note: Net amount from item 1 - 5 work AGAINST trade off shall be clearly stated</p>	lump		sum	
					(PAGE 2) AMOUNT:
					(PAGE 1) AMOUNT:
					TOTAL AMOUNT:

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Stamp / Signature)

Liquidated and Ascertained Damages (LAD): 25/day
For each day the works remain incomplete
(If none stated, then the Contract Administrator
may certify a reasonable sum as compensation
for delay).

Contract period : **3 MONTHS**

Contract / Address:

.....
.....
.....

** Class : I and above

** Category: KPME02,E01,E02

.....
(Official Stamp/ Signature)

Tel. (off)

H/phone

Fax. No