

SUMMARY OF TENDER

Tajuk / Title **ELECTRICAL INSTALLATION WORKS FOR HYDROGENATION ROOM C2.38 2nd FLOOR, FACULTY OF SCIENCE, UNIVERSITI BRUNEI DARUSSALAM**

Bil. Tawaran **UBD/Q/011/2026-[G]**

Tender No.

Bil. No.	Keterangan / Description	Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(€)
	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :				
1	Supply and install 35A 3 phase isolator complete with IP-rated enclosure, cable glands, lugs, ferrules, proper termination, identification labeling, secure mounting in accordance to electrical safety standard (IEC/BS)	nos		5	
2	Supply and install 6mm ² PVC insulated copper cable for 3 phase circuits, complete with routing via PVC conduit/trunking, proper cable support, segregation and dressing.	mtrs		230	
3	Supply, install and wiring of isolator points including mounting, alignment and integration with existing distribution system.	nos		5	
4	Supply and install 13A double switched socket outlets complete with flush box, faceplate, wiring accessories proper earthing, and labeling	nos		21	
5	Supply and install 13A single switched socket outlets complete with flush box, faceplate, wiring accessories proper earthing, and labeling	no		1	
6	Supply and install 2.5mm ² PVC insulated copper cable for socket outlet circuits, complete with routing via PVC conduit/trunking, proper cable support, segregation and dressing.	mtrs		220	
7	Rewiring of existing socket outlet circuits including removal of non-compliant wiring and installation of new cables, re-termination, and full testing and commissioning.	nos		22	
8	To provide comprehensive cable management system including proper segregation of power circuits, organized routing, neat dressing, bundling and securing cables using approved materials support, saddles and cable ties.	lot		1	
9	Testing and commissioning including to provide updated electrical wiring diagram after the installation works.	lot		1	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

Liquidated and Ascertained Damages (LAD): **25/day** For each day the works remain incomplete (If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay). Contract period : **1 week**

Contract / Address:

.....

.....
(Official Stamp / Signature)

Tel. (off)
 H/phone
 Fax. No

** Class : I and above ** Category: E01,E02, M01