Summary Specification			
BIL. SEBUTHARGA/QUOTATION REF.:		UBD/Q/016/2026 (ICTC) - [G]	
TARIKH DIIKLANKAN :	21 April 2026 [Selasa]		
TARIKH TUTUP :	28 April 2026 [Selasa]	JAM:	2 Petang
	DOCUMENT FEE :		B$ 10.00

Important Note:

The Official PDF quotation/tender form will be send via email once UBD Official receipt issued and send to vendors/supplier for confirmation of payment received.

Please take note that the document fee for each of the New and Extended quotations will be BND 10.00 each

Payment Information

Quotations/tenders are identified as follows:
[G] – Kerajaan (Government Account)

Please ensure payment is made to the correct account:
[G] → UNIVERSITI BRUNEI DARUSSALAM [KERAJAAN]

Payment details and account numbers are available under "Mode of Payment" on the UBD website

Note: Please ensure that you provide the correct details when making the payment.

Please email proof of the above payment to helpdesk.epay@ubd.edu.bn. , finance@ubd.edu.bn, eprocurement.support@ubd.edu.bn.

TITLE :		URGENT SUPPLY, DELIVERY, INSTALLATION, CONFIGURATION AND MAINTENANCE OF NETWORK SWITCHES, UNIVERSITI BRUNEI DARUSSALAM
No.	**Quantity**	**SPECIFICATIONS**
1	7 units	C9200L 48-port PoE+, 4 x 1G, Network Essentials Inclusive Power cord. C9200-48P-E
	7 units	C9200 Cisco DNA Essentials, 48-port. 3 Year Term License. C9200-DNA-E-48-3Y
	7 units	CON-5SNT-C92004GE: 3Y SNTC 8X5XNBD 9200L 48 PoE+, 4 x 1G, Net Simplified Campus Automation optimizes the discovery and configuration of devices in your network with a more 3 streamlined simple and easy-to-use automation tool. *Chassis Dimensions 1.73 x 17.5 x 13.8 4.4 x 44.5 x 35.0 *Chassis + FEP + Fan Dimensions (HxWxD) 1.73 x 17.5 x 15.4 4.4 x 44.5 x 39.1
		Scope of work • Implementation and Related Services. Please State Clearly of the following • Deliver install and configurethe to Datacom 2x units will be install and configure in Datacenter for HighPerformance Computing (HPC) 2x unit will be install and configure in Datacentre for MGMT Subnet 1x unit will be install and configure in Datacentre for Additional network points 2x units will be install and configure in Datacom ICTC Lab 6
		• Connect 3 new swicthes to DMZ/SERVER FARM/FACULTY for new High-Performance Computing (HPC) • Item quote must be NEW Not Refurbish • Attach CCIE/CCNA Cert. for Engineer involve in this project • Remove the 3 meter patch code and patch new 1 meterpatch code • Configure security port if required by ICTC • Connect all the swiches to Layer 3 Switches include with SFP and Fibre cable LC-SC • Configure Trunk port and access and create new VLAN inLayer 3 Switches • All item must in in stock • Warranty MUST 3 year for hardware • Must state pricing for Scope of Work