

Summary Specification	
BIL. SEBUTHARGA/QUOTATION REF.:	<u>UBD/Q/019/2026 (ICTC) - [G]</u>
TARIKH DIIKLANKAN :	<u>21 April 2026 [Selasa]</u>
TARIKH TUTUP :	<u>05 Mei 2026 [Selasa]</u> JAM: 2 Petang
DOCUMENT FEE : B\$ 10.00	

Important Note:

The Official PDF quotation/tender form will be send via email once UBD Official receipt issued and send to vendors/supplier for confirmation of payment received.

Please take note that the document fee for each of the New and Extended quotations will be BND 10.00 each

Payment Information

Quotations/tenders are identified as follows:

[G] – Kerajaan (Government Account)

Please ensure payment is made to the correct account:

[G] → UNIVERSITI BRUNEI DARUSSALAM [KERAJAAN]

Payment details and account numbers are available under “Mode of Payment” on the UBD website

Note: Please ensure that you provide the correct details when making the payment.

Please email proof of the above payment to helpdesk.epay@ubd.edu.bn , finance@ubd.edu.bn , eprocurement.support@ubd.edu.bn.

TITLE :		<u>SUPPLY AND INSTALLATION OF CAT6 UTP NETWORK CABLING WORKS FOR UNIVERSITI BRUNEI DARUSSALAM</u>
No.	Quantity	SPECIFICATIONS
1	100 units	Supply and install data point using Cat6 UTP cable run in PVC exposed conduit/casing/ trunking including patch panel
1.1	1 lot	<ul style="list-style-type: none"> *Provide CAT6 UTP for LAN and Access point *Supply RJ-45 connectors, patch panels, faceplates, keystone jacks, conduits, cable trays, and other accessories. *Pull and install CAT6 cables from the network switch to each designated outlet. (estimate 90m per point) *Label both ends of each cable according to the agreed naming convention. *Terminate all cables to RJ-45 keystone jacks at the workstation outlets. *Terminate and organize cables on patch panels at the server/network rack. *Sized appropriately for the number of cables. *Fixed securely to the floor slab or structure. *Laid in a straight and safe path to avoid interference with other services. *Cover and seal all floor trunking using: <ul style="list-style-type: none"> *Metallic or PVC trunking covers. *Flush floor boxes or grommets for workstation outlets. *Proper sealing material to maintain floor integrity and aesthetics. *Restore any disturbed floor surfaces or tiles to original condition or as per client agreement
		<p>WARRANTY</p> <p>Warranty must be at least 20 years</p>