

TENDER NO: UBDCORP/Q/002/2026.

DIIKLANKAN: 28/04/2026 [SELASA]

TARIKH TUTUP: 26/05/2026[SELASA] JAM 11:30 PAGI

DOCUMENT FEE: \$20.00

**IMPORTANT**

The official PDF /tender form will be send via email once UBDCorp Official receipt issued and send to vendors/supplier for confirmation of payment received.

Mode of payment REFER IN UBD WEBSITE

Please take note that the document fee for each of the new and extended quotations will be BND \$20.00 each.

**IMPORTANT NOTE:** Please ensure that you provide the correct details when making the payment. Please email proof of the payment to [office.ubdcorp@ubd.edu.bn](mailto:office.ubdcorp@ubd.edu.bn)

REF: UBDCORP/Q/002/2026

TITLE: INSTALLATION OF OUTDOOR CANOPY FOR THE CORE FOOD COURT

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	<b><u>PRELIMINARIES (Included)</u></b>	<b>1.00</b>	<b>NOS</b>		
1.1	To supply manpower, tools and equipment and carry out the works.				
2	<b><u>SUPPLY OF MATERIALS AND INSTALLATION OF ROOFING WORKS</u></b>				
2.1A	Supply & install 20mm thick White Polycarbonate Roofing Sheets, including fixing screws, washers, sealants, trims, overlaps, cutting and installation complete; OR				
2.1B	Supply & install 20mm thick Glass Roofing, including fixing screws, washers, sealants, trims, overlaps, cutting and installation complete.				
2.2	MS I-Beam 12 x 61½" (38.7 kg/m) used as primary beams, including cutting, welding, lifting and installation complete.				
2.3	MS Circular Pipe Columns 60 6.3mm thick, including fabrication, erection, base plate, anchoring and alignment complete.				
2.4	SHS Purlins 100x50x3.8mm thick, including fixing to beams complete.				

2.5	All connection plates, bolts, nuts, washers, welding consumables and accessories complete.				
2.6	Steel surface preparation & protective painting (1 coat primer + 2 coats finish).				
2.7	Connection of new steel structure to existing building, including brackets and making good.				
3	<b><u>SUPPLY AND CONSTRUCTION OF PAD FOOTINGS</u></b>	<b>6.00</b>	<b>NOS</b>		
3.1	<p>Setting out and excavation for pad footings, including disposal PCC blinding (Grade 15).</p> <p>Reinforced concrete pad footings (Grade 25) complete.</p> <p>High yield reinforcement bars, cut, bend &amp; fix.</p> <p>Formwork to sides of footings.</p> <p>Supply &amp; install anchor/holding down bolts Backfilling and compaction around footings</p> <p>Final site cleaning and making good</p>				
<b>CARRY FORWARD</b>					

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
4	<b><u>SUPPLY AND CONSTRUCTION OF TILE WORKS</u></b>				
4.1	Tile rectification works, including hacking of defective tiles, surface preparation, supply and fixing of replacement tiles, grouting, making good and cleaning complete				
5	<b><u>SUPPLY AND INSTALLATION OF ELECTRICAL WORKS</u></b>				
5.1	Supply, install, test and commission of light fittings complete, including wiring, conduits, accessories and making good				
5.2	Supply, install, test and commission of ceiling fans complete, including wiring, conduits, accessories and making good				
5.3	Supply, install, test and commission of sockets outlet complete, including wiring, conduits, accessories and making good				
6	<b><u>SUPPLY AND INSTALLATION OF OUTDOOR DECORATIVE PANELS</u></b>				
6.1	Supply and install outdoor wall decorative panels, including sub-framing, weather-resistant fixings, cutting, alignment and making good complete.				
<b>TOTAL AMOUNT</b>					