

Summary Specification

BIL. SEBUTHARGA/QUOTATION REF.:	UBD/Q/030/2026 (PAPRSB IHS) - [G]
TARIKH DIIKLANKAN :	05 Mei 2026 [Selasa]
TARIKH TUTUP :	19 Mei 2026 [Selasa] JAM: 2 Petang
DOCUMENT FEE : B\$ 10.00	

Important Note:

The Official PDF quotation/tender form will be send via email once UBD Official receipt issued and send to vendors/supplier for confirmation of payment received.

Please take note that the document fee for each of the New and Extended quotations will be BND 10.00 each

Payment Information

Quotations/tenders are identified as follows:

[G] – Kerajaan (Government Account)

Please ensure payment is made to the correct account:

[G] → UNIVERSITI BRUNEI DARUSSALAM [KERAJAAN]

Payment details and account numbers are available under “Mode of Payment” on the UBD website

Note: Please ensure that you provide the correct details when making the payment.

Please email proof of the above payment to helpdesk.epay@ubd.edu.bn , finance@ubd.edu.bn , procurement.support@ubd.edu.bn.

TITLE :		<u>TO SERVICE, PREVENTIVE MAINTENANCE, PART REPLACEMENT, REPAIR, MODIFICATION, TESTING AND COMMISSIONING FOR LABORATORY EQUIPMENT, PAPRSB IHS UBD</u>
No.	Quantity	SPECIFICATIONS
1	3 units	<p>Cold Room Specification: Brand: Friga-Bohn@, Model: TA4R8P+E1U Serial No: 323540 & 323541 Location: Ground Floor, IHS Main Building Brand: Muller@, Model; MMT035H-C. Location: Level 5, IHS Extension Building Serial No: 1209040518 Scope of work : To check and clean the condenser coil fins To check level of refrigerants and ensure optimal functionality To check the level Oil Compressor, controls, vales, relay, switches To fix water leakage inside Perform a final system functionality test General cleaning and top up gas/refrigerant To replace faulty Fluorescent Bulb (if needed)</p>
2	4 units	<p>Ducted Fumehood Specifications: Brand: Daya Ducted Fumehood Research Lab (G42) Research Lab A (G41) Research Lab 3 (G39) Research Lab 1 (G38) Location: Ground Floor, IHS Main Building Scope of work: Clean the interior work surface and walls,sash, glass, etc Airflow check, inspect controls, check blockages at hood baffles Inspect the fume hood for any physical abnormalities or malfunction To inspect the exhaust Motor Assy. Change the fluorescent lamps assy. Duct and bypass check To fix water leak To do painting of base, panel and metal cladding wall Perform functional and performance test</p>
3	1 unit	<p>Water Purification System Specifications: Brand: Millipore Model: Direct-Q 3 UV Serial Nos: FACB24204 Location: Teaching Lab 1, Main IHS Building Scope of work: To replace smartpak DQ3 and Milipak express 20 To Calibrate the flow and tank level sensor UV timer reset and Screen filter cleaning Functional Check post maintenace and recommendation post maintenance finding Testing and Commissioning</p>

TITLE :		<u>TO SERVICE, PREVENTIVE MAINTENANCE, PART REPLACEMENT, REPAIR, MODIFICATION, TESTING AND COMMISSIONING FOR LABORATORY EQUIPMENT, PAPRSB IHS UBD</u>
No.	Quantity	SPECIFICATIONS
4	1 unit	<p>CO2 Copper Incubator Specifications: Model : CCL-1708-8-UV-CU Serial No: 2021-166183 Location: Level 5, IHS Extension Building Scope of work: Replacement of parts, PM Kit: CO2 Incubator ULPA Filter and Inline Filter for Direct Mounting type Inline Filter, 0.2um (for CO2 and Decon Pump) To Repair, Service and Installation To do general cleaning and decontamination services Testing and Commissioning</p>
5.	1 unit	<p>CO2 incubator Specifications: Model: CCL-240B-8-UV Serial No: 2023-198995 Location: Level 5, IHS Extension Building Scope of work: P(Vt Kit: CO2 Incubator ULPA Filter and Inline Filter for Direct Mounting type Inline Filter, A,2um (for CO2 and Decon Pump) To Repair, Service and Installation To do general cleaning and decontamination services Testing and Commissioning</p>
6	1 unit	<p>CO2 incubator Specifications: Model: CCL-1708-8-C Serial No: 2010-51118 Location: Ground Floor, IHS Main Building Scope of work: Replacement of parts, CO2 IR Sensor Probe PM Kit: CO2 Incubator ULPA Filter and inline Filter for Direct Mounting type Inline Filter, 0.2um (for CO2 and Decon Pump) To Repair, Service and Installation To do general cleaning and decontamination services Testing and Commissioning</p>
7	1 unit	<p>Fumehood Specifications: Model: EFA-4UDRVW-8 Location: 4th Floor, IHS Extension Building Scope of work To install In-line extraction motor 240V 50HZ, 1ph To do electrical wiring and power installation Testing and Commissioning Power Supply 230VAC, 50/60HZ</p>
8	1 unit	<p>External Gas Cylinder Storage Shed Location: Ground Floor, IHS Main Building Scope of Work: Repair and modification works to the existing external gas cylinder storage shed for safety and operational improvement, including: Removal of existing metal frame door Relocation of metal frame and door Fixing and welding of metal door Relocation and extension of 4" drain pipe at the rear of the gas cylinder storage shed Testing and commissioning</p>
9	1 unit	<p>Laboratory Printer Specifications: Model: HP Color Laser Jet Pro MFP M182n Locations: Ground Floor, IHS Main Building Scope of Work: To Fix and replace the faulty part of the printer Testing and commissioning</p>