

**SUMMARY OF TENDER**

Tajuk / Title                    **RECTIFICATION WORK TO VITREOUS CLAY SEWER PIPES FOR CANTEEN AT HEP BUILDING, UNIVERSITI BRUNEI DARUSSALAM.**

Bil. Tawaran                    **UBD/Q/042/2026 - [G]**

Tender No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(g)
	<p><b>Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :</b></p> <p><b>1    <u>PREPARATION WORK, DEMOLITION, DISMANTLING WORK</u></b></p> <p>1.1 Temporary Barriers, Hoarding and Fencing.</p> <p>1.2 Hacking existing walkway, excavation, backfilling and all other necessary works required or make good , clean and wash; clear all debris from the site to receive new finishes.</p> <p><b>2    <u>SANITARY WORKS</u></b></p> <p>2.1 Allow for provision of an approved piling rig and drop hammer suitable for 'Bakau' piling including transportation, erecting, moving about site as necessary and dismantling on completion of piling works.</p> <p>2.2 Supply and drive 'Bakau' piles to an approved set at designated position. Minimum size shall be 65 mm dia. At mid-span x 6 m long. <b>Note: If shorter length are required, the rate shall be calculated on pro-rata basis.</b></p> <p>2.3 Supply and lay 150 mm dia. vitreous clay sewer pipes to BS-EN 295 including excavation, backfill, concrete saddle and all other fittings and work required and <b>connect to new and existing manhole</b> refer to drawing attached.</p> <p>2.4 Construct new mainhole c/w coated cast iron rectangular single seal cover and frame: in accordance to BS-EN 124, sealing cover in grease and fine sand including all necessary excavation, backfilling and connection to new UPVC soil pipe including mortar joints; refer to drawing attached.</p> <p>2.5 Supply labour, plants, tools, equipment, vehicles and other necessary to clean,unblock and desludging existing sanitary pipe system and fittings including greas trap, manhole, floor trap and gully traps <b>inside and outside the canteen.</b></p>				
		Lump		Sum	
		Lump		Sum	
		Lump		Sum	
		Nos		100	
		M		30	
		Nos		3	
		Lump		Sum	
<b>TOTAL AMOUNT</b>					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

Liquidated and Ascertained Damages (LAD): 25/day For each day the works remain incomplete (If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period :

**2 MONTHS**

Contract / Address:

.....  
 .....  
 .....

.....  
 (Official Stamp / Signature)

Tel. (off) .....  
 H/phone .....  
 Fax. No .....  
 .....

\*\* Class : I and above    \*\* Category: KA01,B01,KPB03,KPB15



Location of Pipe