

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **REPLACEMENT OF AUTOMATIC TRANSFER SWITCH & GENERAL SERVICING WORKS FOR CHANCELLOR HALL STANDBY GENERATOR SET, UNIVERSITI BRUNEI DARUSSALAM**

Bil. Sebutharga **UBD/Q/043/2026 - [G]**

Quotation No.

ESTIMATION

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$) (g)
1	<u>PREPARATION WORKS</u> Supply of labour, materials, tools, etc, to demolish, to remove, necessary preparation, make good to all affected area disposed all material and cart away all debris to contractors dump area out from site pe S.O instruction and satisfaction				
2	<u>DISMANTLING WORKS</u> To dismantle existing faulty changeover MCCB 4P including all cables and interconnecting conductors, including existing busbar, connections, lugs, supports and accessories, dismantle of existing Main switch board including all incoming/outgoing connection, clearing away unservicable items away from UBD site	lot		1	
3	<u>SUPPLY, DELIVERY AND INSTALLATION OF NEW AUTOMATIC TRANSFER SWITCH AND MCCB</u> To supply, deliver and install Automatic Transfer Switch (ATS), 4 pole, complete with 800A MCCB, shunt trip coil, control wiring, busbar modification, copper links, cable terminations, panel accessories, enclosure protection covers, labeling and all associated installation works complete in proper working condition.	lots		1	
4	<u>SUPPLY AND INSTALL N200 BATTERIES</u> Supply and install N200 maintenance free batteries complete with new battery terminals, heavy duty battery cables, cable lugs, connectors and all necessary accessories for generator starting system.	nos		2	
5	<u>GENERAL SERVICING WORKS</u> To carry out complete servicing of existing generator set including replacement of engine oil, oil filter, fuel filter and air filter. Inspect and test radiator system, alternator, battery charger, starter system, fuel system, exhaust system, electrical connections and overall generator operation complet with cleaning, tightening and operational testing.	lot		1	
6	<u>WIRING WORKS</u> To supply and install complete wiring works for 800A generator using 2 runs x4C 400mm3 CuXLPE/SWA/PVC Cable complete with 1C 185mm2 earth cable, termination and accessories to complete the works.				
7	<u>TESTING AND COMMISIONING</u> To carry out complete testing and commisioning for the ATS installation works including auto/manual load test.	lot		1	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

3 months

Contract / Address:

.....
.....
.....

.....
(Official Chop / Signature)
Tel. (off)
H/phone
Fax. No
.....

Class and Category: 1 and above / E01, E02, M03