

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **SUPPLY AND INSTALL AIRCONDITIONING UNITS FOR IPS AT ILIA BUILDING, UNIVERSITI BRUNEI DARUSSALAM**

Bil. Sebutharga **UBD/Q/049/2026 - [G]**

Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$) (€)
A	<u>SUPPLY AND INSTALL SPLIT UNITS</u>				
1	To supply, delivery and install (1.5 HP) wall type c/w 20 amps switch socket outlet with Isolator point using 2.5mm ² pvc/pvc cable and other accessories, bracket and items including drain pipe with insulation etc.. to complete the work and terminate to the nearest new sub-Distribution Board.	nos		5	
2	To supply, delivery and install (2.0 HP) wall type c/w 20amps switch socket outlet with Isolator point using 2.5mm ² pvc/pvc cable and other accessories, bracket and items including drain pipe with insulation etc.. to complete the work and terminate to the nearest new sub-Distribution Board.	nos		1	
3	To supply, delivery and install (2.5 HP) cassette type c/w 20 amps switch socket outlet with Isolator point using 2.5mm ² pvc/pvc cable and other accessories, bracket and items including drain pipe with insulation etc.. to complete the work and terminate to the nearest new sub-Distribution Board.	nos		1	
4	To supply, delivery and install (3.0 HP) cassette type c/w 20 amps switch socket outlet with Isolator point using 2.5mm ² pvc/pvc cable and other accessories, bracket and items including drain pipe with insulation etc.. to complete the work and terminate to the nearest new sub-Distribution Board.	nos		1	
5	To supply, delivery and install (5.0 HP) cassette type c/w 35 amps switch socket outlet with Isolator point using 4.0mm ² pvc/pvc cable and other accessories, bracket and items including drain pipe with insulation etc.. to complete the work and terminate to the nearest new sub-Distribution Board.	nos		2	
6	To supply and install refrigerant piping of sizing suit the unit in PVC trunking c/w 3/4" thk close cell insulation (15 ~20 mtrs each Approximate)	lot		10	
7	To supply and install all power from nearest DB using 6mm ² armoured cable to sub-distribution board.	lot		1	
8	To supply and install mounted sub-distribution board to accommodate aforesaid units c/w MCB, MCCB, RCD , submain cable and modification works.	lot		1	
Amount Carried Forward					

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(€)
9	To supply and install cable tray for the 6mm2 armoured cable including other accessories to complete the work.	lot		1	
10	Testing and commissioning of all the above works.	lot		1	
B	<u>MISCELLANEOUS WORKS</u>				
1	Builder's works:				
1.1	Floor projection, provide mobile crane/ scaffolding with additional metal frame etc.	lot		1	
1.2	To make good all the the affected and surrounding area (including hacking, painting, plastering, replace any item to new one & similar).	lot		1	
Amount page 2 :					
Amount page 1 :					
Total amount					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**

For each day the works remain incomplete
(If none stated, then the Contract Administrator
may certify a reasonable sum as compensation)

3 Months

Contract / Address:

.....
(Official Chop / Signature)

Tel. (off)

H/phone

Fax. No

**** Class : I and above**

**** Category: E01, E02 & M03**