

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **ELECTRICAL INSTALLATION WORKS FOR WATER PUMP STATION, UNIVERSITI BRUNEI DARUSSALAM**
 Bil. Sebutharga **UBD/Q/076/2026-[G]**
 Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount	
					(\$)	(g)
A	Preparation Works Supply of labour, materials, tools, etc, to demolish, to remove, necessary preparation, make good to all affected area disposed all material amd cart away all debris to contractors dump area out from site pe S.O instruction and satisfaction					
B	Electrical Works Contractor is compulsory to have direct manpower with valid DES passcard E01/E02 category					
1	To supply and install new floor standing electrical control panel with IP rating, complete with mounting plate, gland plate, cable trunking and internal accessories	lot		1		
2	Supply, deliver and intsaill, programming Pump PLC copmplete with all necessary modules, relay and accessories	nos		3		
3	Supply deliver and install 125A soft starters suitable for existing pump motor	nos		3		
4	Supply deliver and install 150A AC Contactor complete with auxilliary contacts and accessories	nos		3		
5	Supply, deliver and install 250A MCCB complete with mounting and termination works	no		1		
6	Supply, deliver andf install 150A MCCB complete with mounting and termination works	nos		6		
7	Supply deliver and install 63A RCD complete with its accessories	no		1		
8	Supply deliver and install 20A MCB completewith its accessories	nos		6		
9	Supply deliver and install 250A Copper Busbar complete with supports, insulators and shrouding	m		10		
10	Supply deliver and install 95mm ² Copper cable complete with cable glands, lugs and termination	m		5		
11	Supply deliver and install 35mm ² Copper cable complete with cable glands lug and termination	m		40		
12	Supply deliver and install 16mm ² Copper cable with cable glands lugs and termination	m		10		
13	Supply deliver an install 1.5mm ² control cable complete with ferrules, cable markers and termination	set		4		
14	Supply deliver and install 2.5mm ² Insulated copper cable for internal control panel wiring	set		1		
15	Supply deliver and install copper compression cable lugs	nos		30		
16	Supply deliver and isntall 4/0 terminal connectors complete with fixing accessories	nos		40		
17	Supply deliver and install START/STOP push button switch complete with enclosure and accesotries	lot		1		
18	Supply and install internal power and control wiring complete ferrules, cable markers glands and termination for utility meter	lot		1		
	notes: Final connection to incoming utility meter to incoming source shall be carried out by Authorised workers, contractor shall leave sufficient cable length for final termination					
19	Testing and commisioning for all the above works and to provide updated Single line Diagram after all installation works are done.	lot		1		
TOTAL AMOUNT						

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**
 For each day the works remain incomplete
 (If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period
1 months

.....
Contract / Address:

.....
(Official Chop / Signature)

.....
Tel. (off)

.....
H/phone

.....
Fax. No

Class and Category: 1 and above / E01, E02