

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **TO SUPPLY AND DELIVER SERVICE OF ROAD MARKING PAINT FOR ROAD KERB AND ROAD LINE, UNIVERSITI BRUNEI DARUSSALAM.**

Bil. Sebutharga **UBD/Q/096/2026 - [G]**

Quotation No. _____ Page **1** of **4**

Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$)(€)
	<p>Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :</p> <p>REPAINTING WORKS</p> <p>*Note: Contractor to engage with painting license applicator and to provide a warranty certificate of at least 5 years upon completion.</p> <p>**Note: Prepare existing surfaces by removal of existing kerb painting and thermoplastic road lane marking of various widths and types and to prepare existing surfaces by removing all dirt and loose particles, jetwash, oil/grease.</p>				
1	<p>Black and White Road Kerb Painting.</p> <p>Painting kerbs with approved water based weather sheild paints to the Standard Specification of the PWD of various types and sizes as follows:(Refer to DRG No : 1 Road Kerb)</p>				
1.1	Zone 1	Lot	1		
1.2	Zone 2	Lot	1		
1.3	Zone 3	Lot	1		
1.4	Zone 4	Lot	1		
1.5	Zone 5	Lot	1		
1.6	Zone 6	Lot	1		
2	<p>White Reflectorised Thermoplastic Road Marking (Refer to DRG No : 2 Road Marking)</p> <p>Supply and lay white reflectorised thermoplastic road markings of various types and sizes as follows:</p> <p>Broken and continuous lines of widths 100mm, 150mm, 200mm, 250mm and 300mm and thickness between 2-4mm.</p> <p>All other marking eg. Marking at the main roundabout, Arrows, junction marking, pedestrian crossing lines, pavement wordings, numbering and symbols. Etc.</p>				
2.1	Zone 1, To include arrows to indicate the junctions at the roundabout as per S.O. Instruction's.	Lot	1		
(Bring forward to page 3) Total Page 1:					

Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$)(g)
2.2	Zone 2	Lot	1		
2.3	Zone 3	Lot	1		
2.4	Zone 4	Lot	1		
2.5	Zone 5	Lot	1		
3	Yellow Reflectorised Thermoplastic Road Marking (Refer to DRG No : 3) Supply and lay yellow reflectorised thermoplastic road markings of various types and sizes as follows: Arrows, junction marking, pedestrian crossing lines, pavement wordings, chevrons, numbering and symbols. Etc. Rumble Strips of 5-7mm thick				
3.1	Zone 1	Lot	1		
3.2	Zone 2	Lot	1		
4	Flexible Pavement Supply, lay spread and compact asphalt all to MOD General Specification for Flexible Pavement GS. 1/1998 and its Addendum in page QC/1/2 and QC/2/2 in the Contract Specification. Rates shall be inclusive of transportation of all necessary machineries for the entire process of laying, spreading and compaction of hot-mix asphalt binder and wearing courses. Laying, spreading and compacting of asphaltic materials should be done by asphalt supplier / contractor using required or approved asphalt machineries.				
4.1	Supply, construct and install asphaltic concrete road hump complete with excavation, tack coat, asphalt layers, thermoplastic road markings, reflective road studs (where specified), warning signs, and all necessary labour, plant and materials, complete in accordance with the OIC approval. Dimensions * Height: 75 mm * Overall length (direction of travel): 3.7 m * Width: Full carriageway width (leave drainage gaps if required) * Ramp gradient: 1:10 * Asphalt: ACWC/ACBC or equivalent approved mix * Finish: Smooth machine-laid or hand-finished profile * Road markings: Yellow/white chevron markings with reflective glass beads * Signage: "HUMP AHEAD" warning sign on both approaches where required	M	11.40		
(Bring forward to page 3) Total Page 2:					

Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$)(€)
4.2	Supply, construct and install raised pedestrian crossing (speed table) complete with asphaltic concrete, tack coat, road base preparation, compaction, thermoplastic zebra crossing markings, reflective glass beads, warning signs, road markings, traffic management and all associated works in accordance with the Engineer's approval. Typical dimensions: 75 mm high x 3.0 m flat top x 1.2 m ramps each side x full road width. Dimensions * Height: 75 mm * Flat top: 3.0 m * Ramp: 1.2 m each side * Total Length: 5.4 m * Width: Full carriageway	M	10.80		
5	Speed Humps Supply and install heavy-duty modular rubber speed hump, 75 mm high , black and yellow, complete with thermoplastic road markings, reflective road studs (where specified), warning signs, end caps, galvanized anchor bolts, expansion plugs, washers, drilling into existing concrete/asphalt pavement, fixing, alignment, testing and all labour, plant, equipment and materials required to complete the works accordance with the OIC. Typical Specification * Material: Recycled heavy-duty rubber * Colour: Black & Yellow * Height: 75 mm * Width (travel direction): 400–500 mm * Length: To suit carriageway width * Reflective yellow inserts for night visibility * UV-resistant and weather-resistant * Galvanized or stainless-steel anchor bolts * Suitable for concrete or asphalt pavement	M	14.00		
Total Page 3:					
(PAGE 1) TOTAL AMOUNT: Bring forward from page 1					
(PAGE 2) TOTAL AMOUNT: Bring forward from page 2					
Subtotal:					