

UNIVERSITI BRUNEI DARUSSALAM

SUMMARY OF QUOTATION

Tajuk / Title **DESIGN AND FABRICATION OF HANDRAIL AND STAIRCASE FOR CHANCELLOR HALL, UNIVERSITI BRUNEI DARUSSALAM**

Bil. Tawaran **UBD/Q/103/2026 - [G]**

Tender No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$)(¢)
	Supply all necessary and appropriate labor, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below : 1 <u>PREPARATION WORK</u> 1.1 Allow sum for appointment of Competent Designer to design and prepare Architectural drawings and/or detailing's and 3D design for the DESIGN OF MOVABLE STAIRCASE WITH HANDRAIL, MAIN ENTRANCE HANDRAIL and SENATE ROOM HANDRAIL. Also allow for the provision of proposed and as built drawings. 2 <u>FABRICATE MOVABLE STAIRCASE (Main Staircase and 2 Side staircase).</u> 2.1 To fabricate new MOVABLE STAIRCASE (Handrail can be removed) using mild steel structure, mild steel post, with spray paint finish, plywood, wood paneling finish complete with painting. 2.2 Supply and install to staircase new Crest Level cut Loop Role carpet with 8mm-10mm Pile height 1350Gr/m2 Pile weight and woven Polypropylen primary backing and 6mm underlay installation to manufacture instruction c/w all other accessories, adhesive etc. color (red) and pattern to S.O approved 2.3 To fabricate new movable handrail (both sides) using mild steel structure, mild handrail,mild steel post, with spray paint finish. 3 <u>MAIN ENTRANCE HANDRAIL AND BASE (Moveable)</u> 3.1 To fabricate MAIN ENTRANCE HANDRAIL (both sides) using mild steel Structure,mild steel handrail , mild steel post , complete with spray paint finish. 4 <u>SENATE ROOM HANDRAIL (Moveable)</u> 4.1 To fabricate HANDRAIL (one side) using mild steel structure,mild steel handrail , mild steel post , complete with spray paint finish. <u>Note: Please refer to attached diagram for concept design.</u>	Lump		Sum	
		2		Lot	
		2		Lot	
		3		Lot	
		1		Lot	
		2		Lot	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

Liquidated and Ascertained Damages (LAD): **25/day** For each day the works remain incomplete (If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay). Contract period : **3 WEEKS**

Contract / Address:

.....

(Official Stamp / Signature)

Tel. (off)
 H/phone
 Fax. No

** Class : I and above ** Category: KA01, B01

CONCEPT DESIGN

