

Summary Specification	
BIL. SEBUTHARGA/QUOTATION REF.:	UBD/Q/118/2026 (ICTC) - [G]
TARIKH DIIKLANKAN :	14 Julai 2026 [Selasa]
TARIKH TUTUP :	28 Julai 2026 [Selasa] JAM: 2 Petang
DOCUMENT FEE :	B\$ 10.00

Important Note:

The Official PDF quotation/tender form will be send via email once UBD Official receipt issued and send to vendors/supplier for confirmation of payment received.

Please take note that the document fee for each of the New and Extended quotations will be BND 10.00 each

Payment Information

Quotations/tenders are identified as follows:

[G] – Kerajaan (Government Account)

Please ensure payment is made to the correct account:

[G] → UNIVERSITI BRUNEI DARUSSALAM [KERAJAAN]

Payment details and account numbers are available under “Mode of Payment” on the UBD website

Note: Please ensure that you provide the correct details when making the payment.

Please email proof of the above payment to helpdesk.epay@ubd.edu.bn , finance@ubd.edu.bn,
eprocurement.support@ubd.edu.bn.

TITLE :		<u>INSTALLATION, CONFIGURATION, TESTING, COMMISSIONING, INTEGRATION AND MAINTENANCE LAYER 2 SWITCH FOR ICTC .</u> <u>UNIVERSITI BRUNEI DARUSSALAM</u>
No.	Quantity	SPECIFICATIONS
1	7 units	Catalyst 48P *Layer 2, Static Routing, Routed Access (RIP, EIGRP Stub, OSPF - - 1000 routes), PBR, PIM Stub Multicast (1000 routes), PVLAN, VRRP, PBR, CDP, QoS, FHS, 802.1X, MACsec-128, CoPP, SXP, IP SLA Responder, SSO *48 ports full PoE+ *Modular uplink options *PWR-C6-1KWAC 740W *FRU redundant *Network Plug-n-Play *3 Year Term License *4x 1G fixed uplinks *Fixed redundant *FAN-T2= Fan module *Total number of MAC addresses 32,000 *IPv4 routing entries 4,000 *DRAM 4 GB *VLAN IDs 4096 *Features Simplified Campus Automation Simplified Campus Automation optimizes the discovery and configuration of devices in your network with a more streamlined simple and easy-to-use automation tool. *Chassis Dimensions 1.73 x 17.5 x 13.8 4.4 x 44.5 x 35.0 *Chassis + FEP + Fan Dimensions (HxWxD) 1.73 x 17.5 x 15.4 4.4 x 44.5 x 39.1
2	7 units	CON-5SNT-C92004GE : 3Y SNTC 8X5XNBD Catalyst 9200L 48P PoE+, 4 x 1G, Net
3	1 lot	Implementation and Related Services Please State Clearly of the following; • Deliver Install to ICTC Datacenter • Verification of hardware components and software version • Must state pricing for SOW • Item quote must be NEW Not Refurbish • Attach CCIE/CCNA Cert. for Engineer involve in this project

TITLE :		<u>INSTALLATION, CONFIGURATION, TESTING, COMMISSIONING, INTEGRATION AND MAINTENANCE LAYER 2 SWITCH FOR ICTC .</u> <u>UNIVERSITI BRUNEI DARUSSALAM</u>
No.	Quantity	SPECIFICATIONS
		• Re-patch all the network cable and remove faculty faulty/old switches from Datacom • Configuration of management IP address, VLANs, trunk ports, and uplinkinterfaces. • Connect all the switches to Layer 3 Switches include with SFP and Fibre cable • Configure Trunk port and access and create new VLAN in Layer 3 Switches • All item must be in stock
4		WARRANTY Warranty must be at least one year (12 months)