

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **SUPPLY AND INSTALL NEW FLOORING AT PRO-CHANCELLOR ARTS CENTRE, PCAC BUILDING, UNIVERSITI BRUNEI DARUSSALAM.**

Bil. Sebutharga **UBD/Q/146/2026 - [G]**

Quotation No.

Page 1 of 2

Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$) (€)
1	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including ladder and transportation (where necessary), for the proper, safe execution, completion and in accordance to the S.O's instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and install) or otherwise as stated below :	Lump	sum		
1.1	BASE PREPARATION To sanding of the existing flooring and repair exiting cracks on structure and on the flooring surfaces . Any cracks to be filled and repaired using EPIPOX Flooring screed and 500 POX repairing compound materials .				
1.2	To created new expansion joints and clean the floor using approved Manufacturer cleaning agent. Cleaning Method to be done by using Super Casting Flooring system and do under the Supervision of Casting flooring Installer. The flooring to be dried as per the requirement.				
2	WATERPROOFING MOISTURE PROTECTION LAYER To Supply and Apply of EPI Netherlands Moisture Control Waterproofing layer (2 layers) on the prepared Surface.	m ²	374		
3	SUPER CASTING FLOOR COVERING SYSTEM FOR DANCE ACTIVITIES . To Supply and Apply Impregnation layer with AQUAPOX to the absorbent subfloor with approved method of installation as recommended by the Manufacturer.	m ²	374		
4	ACOUSTIC CONTROL SOUND PROOF RUBBER LAYER . To Supply and Install SOUND PROOF RUBBER LAYERS. 4 mm thick using two component approved PU adhesive to the Area underneath, as recommended by the Manufacturer.	m ²	374		
5	POLYURETHANE (PU) LAYERS	m ²	374		
5.1	To supply and Install Polyurethane sealer layer to be applied on the Acoustic control Rubber Layer to protect from moisture and give sound proof as recommended by the Manufacturer and standards.				
5.2	To Supply and Install SEAMLESS Polyurethane and FULLY SOLVENT FREE Casting self levelling Layer with Flooring 60 MP of 2.5 to 3.0 Kg /sqm.				
5.3	To Supply and Install Polyurethane Second Layer , Consisting of single or Multi Colour tone layer system with optional choice of either decorative flakes or designs as per manufacturer instruction and procedure. The colour and design as approved by the S.O.				
(Bring forward to page 2) Total Page 1:					

		Page <u>2</u>		of <u>2</u>	
Bil. No.	Keterangan / Description	Unit Unit	Kuantiti Quantity	Kadar Rate	Jumlah /Amount (\$)(€)
5	POLYURETHANE (PU) LAYERS (Cont'd)				
5.4	To Supply and Install UV-Resistant HARD TOP 100 C/ZG coat of with the Finishes of Mat or Glossy as approved by the SO.				
5.5	To Supply and Install Final finishes of UV- Resistant HARD TOP 200T of with the finishes of Mat or Glossy as approved by the SO.				
6	WOODEN SKIRTING SYSTEM. Supply and Installation of WOODEN SKIRTING all around with the height of 150 mm. including painting. Note: Measurement is only the size of the room, not including vertical riser steps. Measuremnet should be done by the supplier them selves.	M	78		
TOTAL AMOUNT Page 2:					
(PAGE 1) TOTAL AMOUNT: Bring forward from page 1					
Subtotal:					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period
4 Month or 120 Days

Contract / Address:

.....
.....
.....
.....

.....
(Official Chop / Signature)

Name:
Tel. (off)
H/phone:
Email:

**** Class : I and above**

**** Category: B01**