

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **TO PROVIDE GROUND PREPARATION WORKS FOR PLANTING NEW SAPLING FOR 5 MONTHS AT UNIVERSITY BRUNEI DARUSSALAM**

Bil. Sebutharga **UBD/Q/164/2026-[G]**

Quotation No.

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantiti	Jumlah (\$)(RM)
1	<u>GROUND PREPARATION WORKS</u>				
1.1	Excavate, cart away and removal of all roots and the existing soil for planting pit, breaking any hard ground for proper aeration and ensuring sufficient drainage as indentified & instructed by the S.O.				
1.1.1	(area 0.3m x 0.3m x 0.3m)	No		330	
1.1.2	(area 0.3m diameter x 1.0m deep)	No		290	
1.2	To supply and backfill with quality topsoil with min. pH 5.0 including Allow for lime application according to the level of acidity soil (2kg/m3 of topsoil).To mix Organic Soil Conditioner with topsoil in planting holes (2 bags (20kg)/m3) and To mix granular coated resin slow release fertilisers with all planting media at rate of 2kg/m3.				
1.2.1	(area 0.3m x 0.3m x 0.3m)	No		330	
1.2.2	(area 0.3m diameter x 1.0m deep)	No		290	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day** For each day the works remain incomplete (If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

Contract period

5 months

Contract / Address:

.....
.....
.....

.....
(Official Chop / Signature)
Tel. (off)
H/phone
Fax. No
.....

**** Class : I and above**

****Category : KPB12**