

Summary Specification	
BIL. SEBUTHARGA/QUOTATION REF.:	UBD/Q/181/2026 (ICTC) - [G]
TARIKH DIKLANKAN :	<u>15 September 2026 [Selasa]</u>
TARIKH TUTUP :	<u>22 September 2026 [Selasa]</u> JAM: 2 Petang
DOCUMENT FEE :	B\$ 10.00

Important Note:

The Official PDF quotation/tender form will be send via email once UBD Official receipt issued and send to vendors/supplier for confirmation of payment received.

Please take note that the document fee for each of the New and Extended quotations will be BND 10.00 each

Payment Information

Quotations/tenders are identified as follows:

[G] – Kerajaan (Government Account)

Please ensure payment is made to the correct account:

[G] → UNIVERSITI BRUNEI DARUSSALAM [KERAJAAN]

Payment details and account numbers are available under “Mode of Payment” on the UBD website

Note: Please ensure that you provide the correct details when making the payment.

Please email proof of the above payment to helpdesk.epay@ubd.edu.bn , finance@ubd.edu.bn,
eprocurement.support@ubd.edu.bn.

TITLE :		URGENT SUPPLY, DELIVERY, INSTALLATION, CONFIGURATION, TESTING AND COMMISSIONING OF SUPERVISOR MODULES FOR IHS MAIN BUILDING, UNIVERSITI BRUNEI DARUSSALAM.
No.	Quantity	SPECIFICATIONS
1	2 units	C9400-SUP-1: 9400 Series Supervisor 1 Module C9400-PWR-3200AC :9400 Series 3200W AC Power Supply
2	2 units	Scope of Work – Installation of 9400 Series Supervisor 1 Module and 9400 Series 3200W AC Power Supply This unit is required urgently due to ongoing network connectivity issues affecting operations • Pre-installation assessment and compatibility verification of chassis, supervisor engine, IOS-XE version, and power capacity. • Update the line card to latest firmware • Backup all the configuration before replacing the faulty unit • Installation of 9400 Series Supervisor 1 Module and 9400 Series 3200W AC Power Supply. • Installation and verification of SFP/SFP+ transceivers. • Configuration of switch interfaces, VLANs, trunking, EtherChannel/LACP, and port parameters as required. • Fiber patching, labeling, and cable management. • Operational testing and verification of all installed ports. • Migration/cutover of existing network connections. • Health check, log review, and performance verification.
3	1 lot	•All equipment supplied must be genuine and new •Location to install IHS MAIN building •Maintenance Support includes technical support for the 9400 platform, configuration assistance, fault diagnosis, software and new switches installation •The quoted item must be available in stock
4		WARRANTY Warranty must be at least one year (12 months)