

Summary Specification	
BIL. SEBUTHARGA/QUOTATION REF.:	UBD/Q/182/2026 (ICTC) - [G]
TARIKH DIKLANKAN :	<u>15 September 2026 [Selasa]</u>
TARIKH TUTUP :	<u>22 September 2026 [Selasa]</u> JAM: 2 Petang
DOCUMENT FEE :	B\$ 10.00

Important Note:

The Official PDF quotation/tender form will be send via email once UBD Official receipt issued and send to vendors/supplier for confirmation of payment received.

Please take note that the document fee for each of the New and Extended quotations will be BND 10.00 each

Payment Information

Quotations/tenders are identified as follows:

[G] – Kerajaan (Government Account)

Please ensure payment is made to the correct account:

[G] → UNIVERSITI BRUNEI DARUSSALAM [KERAJAAN]

Payment details and account numbers are available under “Mode of Payment” on the UBD website

Note: Please ensure that you provide the correct details when making the payment.

Please email proof of the above payment to helpdesk.epay@ubd.edu.bn , finance@ubd.edu.bn , eprocurement.support@ubd.edu.bn.

TITLE :		URGENT SUPPLY, DELIVERY, INSTALLATION, CONFIGURATION AND MAINTENANCE OF DISTRIBUTION SWITCHES, UNIVERSITI BRUNEI DARUSSALAM
No.	Quantity	SPECIFICATIONS
1	7 units	C9200L 48-port PoE+, 4 x 1G, Network Essentials Inclusive Power cord. C9200-48P-E
2	7 units	C9200 Cisco DNA Essentials, 48-port. 3 Year Term License. C9200-DNA-E-48-3Y
3	7 units	CON-5SNT-C92004GE: 3Y SNTC 8X5XNBD 9200L 48 PoE+, 4 x 1G, Net Simplified Campus Automation optimizes the discovery and configuration of devices in your network with a more 3 streamlined simple and easy-to-use automation tool. *Chassis Dimensions 1.73 x 17.5 x 13.8 4.4 x 44.5 x 35.0 *Chassis + FEP + Fan Dimensions (HxWxD) 1.73 x 17.5 x 15.4 4.4 x 44.5 x 39.1
4	1 lot	Scope of work • Implementation and Related Services. Please State Clearly of the following • . Deliver Install and configure to Datacome 2x units will be install and configure in Datacenter for DMZ. 2x unit will be install and configure in Datacenter for MGMT Subnet 2x unit will be install and configure in HEP for Additional network points 1x units will be install and configure for JOOMPA and UBD CENTRAL.
		• Connect 3 new swiches to DMZ/SERVER FARM/FACULTY for new High-Performance Computing (HPC) • Item quote must be NEW Not Refurbish • Attach CCIE/CCNA Cert. for Engineer involve in this project • Remove the 3 meter patch code and patch new 1 meter patch code • Configure security port if required by ICTC

TITLE :		<u>URGENT SUPPLY, DELIVERY, INSTALLATION, CONFIGURATION AND MAINTENANCE OF DISTRIBUTION SWITCHES, UNIVERSITI BRUNEI DARUSSALAM</u>
No.	Quantity	SPECIFICATIONS
		• Connect all the swiches to Layer 3 Switches include with SFP and Fibre cable LC-SC
		• Configure Trunk port and access and create new VLAN in Switches
		• All item must in in stock
		• Warranty MUST 3 year for hardware
		• Must state pricing for Scope of Work
5		WARRANTY Warranty must be at least one year (12 months)