

**RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION**

Tajuk / Title **RELOCATION OF HIGH VOLUME LOW SPEED FAN FROM FEMALE HOSTEL CANTEEN TO MAIN I.H.S SUNKEN YARD,
UNIVERSITI BRUNEI DARUSSALAM**

Bil. Sebutharga **UBD/Q/184/2026-[G]**
Quotation No.

DRAFT

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah / Amount (\$) (g)
	Supply of labour, materials, tools, etc, to demolish, to remove, necessary preparation, make good to all affected area disposed all material and cart away all debris to contractors dump area out from site per S.O instruction and satisfaction Note: The contractor shall carry out site visit inspection and take into account all aspects and conditions of site before submitting his quotation. The contractor must fill this schedule at the time of tendering. Contractor having submitted their prices are considered as having visited the site. No claims for additional payment will be entertained on the ground of misunderstanding or misinterpretation of the conditions, measurement etc.				
1	To dismantle, disassemble, take down existing big Ash fan, control panel at female Hostel working at high level.	lot		1	
2	To make good ceiling, wiring tidying up works at female Hostel after removal of Big Ash fan working at high level inclusive of touch up paint work on the affected area.	lot		1	
3	Rental, provide, erect, install inclusive of disassemble after works completion using 6 mtrs Aluminium scaffolding with proper bracing Arms, stabilizing support, steps, landing and roller wheel/stopper, full-body safety harness for worker for the installation of Big Ash fan and making good of ceiling works.	lot		1	
	Transport of Big Ash fan from female Hostel to IHS inclusive of protection of items.	lot		1	
4	To supply and install 3x4mm ² PVC cable in PVC conduit from nearest DB to controller inclusive of all hacking and making good works, upgrading DB and modification for 2P RCD/MCB and termination works.	lot		1	
5	To supply and install 3x4mm ² PVC cable in PVC conduit from controller to Big Ash fan inclusive of all hacking and making good works.	lot		1	
6	To fabricate, supply and install 1.2mtr long square MS bracket coated with 4 holding down bolt, safety wire, anti-rust paint with 2 layer of finish paint inclusive of Anchoring into concrete slab for the mounting of big Ash fan working at high level.	lot		1	
7	To cut open existing ceiling for access for above installation works, working at high level for the installation of custom make flush bracket flush inclusive of making good plaster ceiling and paint works on affected area.	lot		1	
8	Installation of Big Ass fan and controller working at high level inclusive all termination works.	lot		1	
9	Rental, provide, erect, install inclusive of disassemble after works completion using 9 mtrs Aluminium scaffolding with proper bracing Arms, stabilizing support, steps, landing and roller wheel/stopper, full-body safety harness for worker for the installation of Big Ash fan and making good of ceiling works.	lot		1	
10	Provide, install and maintain temporary safety barricade/exclusion zone around the work area, complete with warning signage and safety tape, to prevent unauthorized access and pedestrian movement during high-level HVLS fan installation. Dismantle and remove after completion of works.	lot		1	
11	Supply, deliver and install inlet and outlet aluminium ventilation grille existing for door inclusive of all masonry works, opening and touch up if required.	lot		1	
15	Testing and commissioning for all the above work	lot		1	
TOTAL AMOUNT					

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

.....
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): **25.00/ day**
For each day the works remain incomplete
(If none stated, then the Contract Administrator may certify a reasonable sum as compensation for delay).

2 weeks

Contract / Address:

.....
.....

.....
(Official Chop / Signature)

Tel. (off)

H/phone

Fax. No

Class and Category: 1 and above / E01, E02, M01