

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah /Amount (\$) (€)
1	Bill No.1 <u>AIR CONDITIONING MAINTENANCE WORKS</u> The Schedule is for routine maintenance and servicing of Air Conditioning system / Plants/ Equipment specified in Schedule of equipment. We are required to include prices for different category/ type of maintenance terms as WEEKLY, MONTHLY and Annual Maintenance" for a period of 12 months We shall be required to carry out 11 nos. "Monthly Maintenance" and 1 annual service. The maintenance and servicing shall be carried out as specified in the Basic Guideline for Maintenance of Air-Conditioning System. All the prices shall include cost of Maintenance Teams, any special equipment/tools deem necessary to carry out works and transportation The prices quoted below for this maintenace includes the labour to replace Parts (material to be supplied by client). Attendance Teams, routine services, operation, any specialist visit to site and standby (if required) during whole contract period. The quoted rates below are included all Cost to fix all minor defect Note: Tenderer must have minimum each one Mechanical Engineer (M01), One Electrical Engineer (E01, E02 and E03) and 2 x Technician (M01), tenderer must submit the valid Registration ID with relevant department.				
a	<u>SCHEDULE OF EQUIPMENT</u> Water cooled chiller (1,2,4 and 5)	mths		12	
b	Primary Chilled water pumps - 5 nos	mths		12	
c	Secondary Chilled water pumps - 5 nos	mths		12	
d	Condensing Water Pumps - 5 nos	mths		12	
e	Cooling Tower - 5 nos	mths		12	
f	Ventilation system (main plant)	mths		12	
g	Cooling tower filtration system - 5 nos	mths		12	
h	Cooling tower water storage tank	mths		12	
i	Main MCCB and Control Panel	mths		12	
2	Bill No.2 <u>WATER TREATMENT</u> The Schedule is for routine water treatment of condensing and chilled water systems. We are required to include prices for different categories/types of maintenance terms as " Weekly- Testing pH and TDS, Monthly Test, Half-Yearly Legionella Bacteria Test, Monthly Maintenance and Monitoring of Chemical Dosing System, The Maintenance shall be carried out every month for a period of 12 months. The maintenance and servicing shall be specified in the Basic Guideline for Maintenance of Air- Conditioning System and Particulars Condition and as follows. a. Weekly Testing pH and TDS , Total Hardness and corrosion inhibitor b. Monthly Carry out all the test as specified in Scope of works and Particular Condition (Except Legionella Bacteria) at local laboratory / on site . 2.2 Half-Yearly Test for Legionella Bacteria by approved type laboratory only. 2.3 Monthly Maintenance of Chemical Dosing system 2.4 Full washout condensing water system works replenish with fresh water and add approved adequate amount of chemical. 2.5 Supply and approved ECO-friendly type Corrosion inhibitor and bio side chemical, copper and mild steel corrosion monitor coupons, safety equipment, water sample testing etc for the whole contract period. 2.6 Full washout chilled water system works replenish with fresh water and add approved adequate amount of chemical 2.7 To supply manufacture's genius replacement gasket , descale chiller condenser barrel and cooler barrel using rotor jet machine (no manual Roding is allowed) and use only apposed type eco friendly chemical. (4 Nos of Chiller)	months		12	
		times		2	
		months		12	
		times		2	
		months		12	
		time		1	
		time		1	
	JUMLAH DIBAWA DARI DEPAN / AMOUNT BROUGHT FORWARD				

Bil. No.	Keterangan / Description	Unit Unit	Kadar Rate	Kuantiti Quantity	Jumlah (\$) (€)
	JUMLAH DIBAWA DARI DEPAN / AMOUNT BROUGHT FORWARD				
	Bill No3				
3	<u>CONTRACTOR'S SUPERVISOR & MANPOWER</u>				
3.1	To include prices for the manpower to carry out Housekeeping and daily monitoring of system as equipment as specified including labour, tools and transportation as follows:	months		12	
a	To breakdown attendance to any complaint during normal office hours within 2 hours from the receipt of complaint and run back the system to normal in case no material is required, submit repair report to client representative				
b	The maintenance team is on-call basis 24Hr/7D a week, the team shall make a daily visit to the site minimum of once every day excluding Sundays and public holidays, responsible for good house-keeping of the chiller yards and monitoring and daily log sheets reading of the Air-Conditioning Plants /Equipment update and client representative on accordingly, the works shall carry out as specified in the Basic Guideline and Particulars Condition.				
c	Provide for labour including transportation for Standby after office hours, Sunday & public holiday, works to be carried out after working hrs as per instructions by client SO, (estimated 120 man-hours and any additional deem necessary included in the offer prices)				
	Bill No. 4				
4	<u>GENERAL REPLACEMENT PARTS</u>				
	To cost in all the listed below items as follows from the date of commencement to the end of the contract				
a	All types of Lubricants and grease etc				
b	Any corrosive paint and any rust paints for annual service/ routine touch up				
c	Nitrogen gas for leak testing				
d	Oxy /acc gas for welding /cutting				
e	Cleaning chemicals				
f	Any alge chemical/tables				
g	Industrial adhesives	months		12	
h	V belts of any size /type for all the cooling towers etc.				
i	Airfilters				
j	Refrigerant filter driers				
TOTAL AMOUNT					

Bill No	Keterangan / Description	Jumlah /Amount
		(\$) (¢)
	Summary of prices	
Bill 1	AIR CONDITIONING MAINTENANCE WORKS	
Bill 2	WATER TREATMENT	
Bill 3	CONTRACTOR'S SUPERVISOR & MANPOWER	
Bill 4	GENERAL REPLACEMENT PARTS	
TOTAL AMOUNT		

Validity Offer : **6 (six) months (from the date of quotation)**

Liquidated and Ascertained Damages (LAD): **25.00/ day**
 For each day the works remain incomplete
 (If none stated, then the Contract Administrator
 may certify a reasonable sum as compensation
 for delay).

Contract period

12 months

Contract / Address:

.....

.....
 (Official Chop /
 Signature)

Tel. (off)

H/phone

Fax. No

**** Class : I and above**

**** Category: M03, MO1, E01, E02 and P05**