RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION

Tajuk / Title **SUPPLY AND INSTALL NEW ACOUSTIC CEILING AND FLOORING AT ILIA CONFERENCE ROOM, GROUND FLOOR**

Bil. Sebutharga **UBD/Q/ 238 /2026**
Quotation No.

Bil. No.	**Keterangan /** Description	**Unit** Unit	**Kadar** Rate	**Kuantiti** Quantit	**Jumlah** /Amount ($) (¢)
	Supply all necessary and appropriate labour, approved materials, proper and safe hand and/or powered tools and equipment including scaffolding and transportation (where necessary) for the proper, safe execution, completion and in accordance to the S.O's Instructions and satisfaction, for the following scope of works (to remove/disconnect/demolish existing, fabricate, supply and Install) or otherwise as stated below :				
A	**DEMOLITION & DISMANTLING WORKS**				
1	Supply of labour. materials, tools, etc. to demolish/to remove smoke detectors, lighting (wiring and fittings), air return fitting and etc with relocation of electrical component fittings,airconditioning units with condenser. network point, AV system and etc, carpet, wall panelling, existing ceiling and treatment to existing soffit, wall, flooring and other elements for smooth surface with necessary approved painting, necessary preparation and make good to all affected area, disposed all materials and cart away all debris to contractors dump areas per S.O. instruction and satisfaction for the purpose of this renovation works.	LUMP		SUM	
				(PAGE 1) TOTAL AMOUNT: Bring forward to page 2	**$ -**

B	**CEILING**				
1	To supply and install new suspended acoustic ceiling panels in multiple-sized rectangular designs at a uniform level, complete with G.I. framing, hangers, brackets, suspension system securely fixed to the existing concrete soffit, approved finishing and all other necessary works required. Design and height subject to S.O approval	m^2		227	**$** -
C	**PAINTING (Painting to existing wall, new wall, existing ceiling and new ceiling.)**				
1	To prepare surface to be repainted by removal of all loose paints, nail, etc. and plaster / putty all imperfection and sanding to S.O satisfaction to manufacture spec and procedure	LUMP		SUM	
2	Supply all labour, materials, tools, etc. to prepare, clean and apply Juton 1 coat of primer sealer, 2 undercoat and 2 finishing coats strict accordance to Manufacturer's instructions; color to S.O.'s approval.	LUMP		SUM	
				(PAGE 2) TOTAL AMOUNT:	**$**
				Bring forward to page 3	
D	**M & E WORKS**				
1	Re-arrangement and make good existing exposed electrical wiring, conduits pipe, complete with proper cable management system including cable tray, trunking, supports, conduits, cable dressing and rerouting works for open ceiling concept installation.	Lot		1	
2	To supply and install new sub-distribution board (DB) for the lab, complete with Main Switch, RCDs, MCBs and proper wiring sizing to independently control lightings & ACs including all accessories and items to complete the work including testing and commissioning.	Lot		1	
3	Supply and install black finish 2M LED magnetic track lighting system for the open space area complete with magnetic tracks, 6 nos LED track spotlights 15-20W, CCT 4000-6500K, drivers, connectors, joints, wiring, supports and accessories, Lighting installation shall be wired using 1C 1.5mm^2 PVC insulated copper cable complete with 10A/16A MCB protection. Design to be approved by SO.	Set		2	
4	To supply and install 25w LED downlight abci approved 4000-6500K CCT or equivalent including driver with all necessary accessories including wiring works, wiring and terminate to the nearest existing Distribution Board. Design to be approved by SO.	Nos		65	
5	To supply and install 4 gang 2 way switch with frame and 2.5mm2 pvc/pvc conduit cable ring circuit (3x1C) all necessary accessories inlcuding hacking and make good to complete the work. Design to be approved by S.O	Nos		4	
6	To supply, delivery and install 5.0 hp cassette type c/w 20 amps switch socket outlet with Isolator point using 4.0 mm2 pvc/pvc cable and other accessories, bracket and items including drain pipe with insulation etc.. to complete the work and terminate to the nearest new Sub-Distribution Board with testing and commissioning. **Note : To attach ABCi approved brand.**	Nos		3	
7	Provide scalffolding, hacking and opening for laying new cables/piping and make good after the work completed including painting work as per original finish.	Lot		1	
8	Testing and commissioning for all the above works	Lot		1	
				(PAGE 3) TOTAL AMOUNT:	**$** -

(PAGE 1) TOTAL AMOUNT:	**$**	**-**
(PAGE 2) TOTAL AMOUNT:	**$**	
(PAGE 3) TOTAL AMOUNT:	**$**	**-**
TOTAL AMOUNT:	**$**	**-**

Validity Offer : **6 (six) months (from the date of quotation)**

Defect Liability period: **6 (six) months**

……
(Official Chop / Signature)

Liquidated and Ascertained Damages (LAD): 25/day
For each day the works remain incomplete
(If none stated, then the Contract Administrator
may certify a reasonable sum as compensation
for delay).

Contract period : 2 MONTHS

Contract / Address:

……

……

……

****Class: 1 and above**

****Category: B01, E01**

……
(Official Chop / Signature)

Tel. (off) ……

H/phone ……

Fax. No ……